

REPORT of SURVEY for REPAIRS.

22207

No. 430 Survey held at London Date 14th January 1858
 on the Ship "Sir James" Master _____
 Tonnage 670 Built at Sunderland When built 1833
 By whom built 646 Owners Storer & Co
 Port belonging to London Destined Voyage Sydney
 If Surveyed Afloat or in Dry Dock Union dry Dock,

Last Survey, No. 19609 Port London Classed AT
 55

REPAIRS

Now done, - Yellow Metal sheathing shipped off the bottom. Added, six pairs of diagonal and one pair of vertical iron Riders extending from the upper deck clamps to the lumber shake and fastened with Yellow Metal bolts. six pairs of wood lodging knees fitted to upper deck beams and under the scarp of Waterway, the ship hung in shores, recaulked from the Keel upwards including the Waterway and three seams of deck, Yellow Metal sheathing renewed on Sels.

Present Condition of the

Decks <u>good</u>	Treenails <u>good</u>	Windlass and Capstan <u>good</u>
Waterways <u>"</u>	Breasthooks and Stemson <u>good</u>	Pumps <u>"</u>
Comings <u>"</u>	Transoms, Pointers, and Crutches <u>where</u>	Boats <u>"</u>
Upper Deck Beams & Fastenings <u>good</u>	Timbers of the Frame <u>seen</u>	Masts, Yards, &c. <u>good order</u>
Lower Deck Beams & Fastenings <u>where seen</u>	Keelsons <u>good</u>	Sails <u>and sufficient</u>
Planksheers <u>good</u>	Clamps and Shelves <u>"</u>	Anchors No. of <u>3 B, 1 S, 2 K,</u>
Sheerstrakes <u>"</u>	Ceiling <u>"</u>	Cables <u>sufficient good</u>
Topsides <u>"</u>	Rudder <u>"</u>	Hawsers and Warps <u>"</u>
Wales <u>"</u>	When put on <u>now</u>	Standing & Running Rigging <u>"</u>
Plank (Bottom) and Counter <u>"</u>		

General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways. good where tried

This vessel is now in good and efficient condition and eligible in our opinion to remain as Classed AT

The Amount of Fee.....£ : : is received by me,

Special..... : :

Certificate (if required) : :

Committee's Minute 11th March 1858

Character assigned AT

Special Extra Attendance } £ 3.0

J. H. Giltman
 Thos. M. Brown