

22353

REPORT of SURVEY for REPAIRS.

Rev. 12.4.59

No.

298

on the

Survey held at

London

Date

Feb^{ry} 25th to Mar^{ch} 7 1859

Tonnage

215

Built at

Sunderland

When built

1851

By whom built

Owners

J^r Bonus

Port belonging to

London

Destined Voyage

If Surveyed Afloat or in Dry Dock

Limetown dry dock and W. J. dock

Last Survey, No.

21553

Port

London

Classed

G A 1.

REPAIRS

of Damage now done. 6 roughsties on the Port side from forward to the gangway and 42 put of rail and barking in way of the same renewed, part new barking on the Starboard side, one new hawse pipe and new hawse cheeks on each side, head rails and barking repaired, Windlass overhauled, 8 throat bolts to hold beam hanging trees renewed of metal on each side, one broken Iron tree repaired, refitted and bolted, pintles and braces rebolted, and the upper one of Iron repaired, yellow-metal stripped and vessel caulked from keel over all fore and aft and the metal on bottom renewed on paper. Additional work now done. Two cheeks worked on plank sheers the aft side of hawse timbers, an Iron hook fitted over bowsprit, two planks of deck next the waterways renewed and Car heads repaired and fitted on new cheeks.

Present Condition of the

Decks	caulked	Treenails		Windlass and Capstan	good
Waterways	"	Breasthooks and Stemson		Pumps	"
Comings	good	Transoms, Pointers, and Crutches		Boats	good and sufficient
Upper Deck Beams & Fastenings	good	Timbers of the Frame	good	Masts, Yards, &c.	"
Lower Deck Beams & Fastenings	where seen	Keelsons	where	Sails	"
Plank sheers	good	Clamps and Shelves	seen	Anchors	No. of 303. 13. 11.
Sheerstrakes	caulked	Ceiling		Cables	good and complete
Topsides	"	Rudder		Hawseys and Warps	"
Wales	"	Copper	Y.M. When put on now done on paper	Standing & Running Rigging	"
Plank (Bottom) and Counter	"	Caulking of Bottom, Deck, & Waterways.	good where tested		

General Observations and Opinion,

This vessel is now in good Condition, and in my opinion eligible to remain as Classed G A 1.

The Amount of Fee.....£ : 10 : - is received by me,

Special..... 2 : 2 : -

Certificate (if required) : 5 : -

Committee's Minute

15th April

1859

Character assigned

G A 1

Charge for attendance £ 2. 2.



© 2019

Lloyd's Register Foundation

LN64-0033