

REPORT of SURVEY for REPAIRS.

No. 158 Survey held at London Date May 18th to June 27th 1859
 on the S. "Jane Ewing" Master L. Stanton * Cornice
 Tonnage 433 Built at Greenock When built 1850
 By whom built _____ Owners Duff & Co. * W. M. Inroy
 Port belonging to Liverpool Destined Voyage _____
 If Surveyed Afloat or in Dry Dock Gun dry dock * Vide L'pool Letter 6/2/61

Last Survey, No. 21754 Port London Classed 13 A 1

REPAIRS

Now done: Yellow metal sheathing stripped -
 In consequence of decay: Fifty four. Kant timbers, first and second futtocks from half deck hatch aft renewed with Teak and English Oak - After piece of Kelson, upper piece of deadwood, inner stern post and sternson knee renewed with the same, also forty-four cross, twelve long and twenty four keel chocks fitted of the same; nearly the whole of the ceiling in the lower hold from the mainmast fast and five after hoops of bottom plank new of Teak, rethenailed from the upper part of bilge to keel from fore side of main hatch right aft, also in way of new work - Eight Iron riders and two crutches aft refitted & bolted with Yellow metal, keels of Cant timbers aft and timber strakes from main mast aft through bolted - Two new pumps and Hawse boxes fitted - lower deck laid of 3 in Pine and caulked - Hung in shores, caulked from keel to metal line and Y. In renewed on Felt

Decks		Treenails		Windlass and Capstan	
Waterways	good	Breasthooks and Stemson	good	Pumps	
Comings		Transoms, Pointers, and Crutches		Boats	
Upper Deck Beams & Fastenings	do	Timbers of the Frame	where seen	Masts, Yards, &c.	In good order
Lower Deck Beams & Fastenings	where seen	Keelsons	do	Sails	and
Planksheers		Clamps and Shelves	do	Anchors No. of	sufficient
Sheerstrakes	do	Ceiling	do	Cables	
Topsides	do	Rudder	do	Hawsers and Warps	
Wales	do	Copper <u>Y.M. on F.</u> When put on	now	Standing & Running Rigging	
Plank (Bottom) and Counter	do				

General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways. Good where tried

This vessel is now in good condition and is eligible in our opinion to remain classed 13 A 1

Thos. W. Wain

The Amount of Fee.....£ 1 : - : - is received by me,

Special..... 5 : 5 : -

Certificate (if required) : 5 : -

Committee's Minute 12th July 1859

Character assigned 13 A 1

record repairs

