

22671

# REPORT of SURVEY for REPAIRS.

Damage &c

No. 64 Survey held at London Date July 18<sup>th</sup> to Aug 15 1859  
on the Ship "Seymouth Castle" Master J. M<sup>c</sup> Alister

Tonnage 604 Built at Greenock When built 1831  
By whom built 682 Owners J. Thomson

Port belonging to Glasgow Destined Voyage Calcutta

If Surveyed Afloat or in Dry Dock Globe Dry Dock

Recd 23.9.59  
J. M<sup>c</sup> Alister

Last Survey, No. 21301 Port London Classed 13A.1

## REPAIRS

Now done, the keel stripped, Caulked and sheathed with Yellow Metal on felt; hung in shores and a false keel added of Pitch Pine. - Main Mast renewed.

Repairs - The Stag Kelson renewed from the Fore Mast to abaft the Main Mast with Seal, the Main Kelson trimmed down to anchor stock shape in midships, and the Stag Kelson fitted to it, and bolted with seven 1" Yellow Metal thir' bolts, the remaining Stag bolted with 1" Iron passing thro' the Main Kelson -

In the Fore body on the larboard side, eleven Cant timbers, five second futtocks, two thirds ~~and~~ one first futtock, and twenty two beveling Chocks, on the Starb<sup>d</sup> -

P. S. O.

Present Condition of the

ks  
Waterways } Good  
omings }  
Upper Deck Beams & Fastenings } firm  
Lower Deck Beams & Fastenings }  
Planksheers }  
Sheerstrakes } Good where seen  
Topsides }  
Wales }  
Plank (Bottom) and Counter Caulked

Treenails Part new  
Breasthooks and Stenson good  
Transoms, Pointers, and Crutches good  
Timbers of the Frame Part new  
Keelsons good  
Clamps and Shelves good where seen  
Ceiling Part new  
Rudder good  
Galvanic  
Copper on felt When put on new

Windlass and Capstan  
Pumps } Good and suff<sup>t</sup>  
Boats }  
Masts, Yards, &c. New Main  
Sails  
Anchors No. of }  
Cables } Good and suff<sup>t</sup>  
Hawsers and Warps  
Standing & Running Rigging

General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways. good where tested -

She is now fit in my opinion to remain as classed 13A.1.  
P. W. Alister

The Amount of Fee.....£ 2 : - : - is received by me,

Special..... 3 : 3 : -

Certificate (if required) : : -

Committee's Minute 4<sup>th</sup> October 1859

Character assigned 13A.1

Charge £ 3. 3. for extra attendance

Damage £ 4. 4. -



22671 Lon

side, nine Cant timbers, two first futtocks, three  
seconds, three thirds, and twenty three chocks,  
renewed, all with Seal, excepting two second  
futtocks of English Oak - All the fore boards  
of Ceiling from the Lower deck Clamps down  
renewed with Seal - the trenails thro' the  
new work of Stringy Bark -

J. B. Maymouth



© 2019

Lloyd's Register  
Foundation