

REPORT of SURVEY for REPAIRS.

Change of Owners.

No. 66 on the Barque Mersey. Survey held at London Date Nov^r 8th 1859
 Tonnage 607 Built at Nova Scotia When built 1851.
 By whom built W. Crowell. Owners W. Crowell.
 Port belonging to London Destined Voyage
 If Surveyed Afloat or in Dry Dock New Crane / Dry Dock.

Last Survey, No. 14250

Port Spain

Classed 4 B.

REPAIRS

At this date, Stripped off the Line. tried the Caulking. Spotted the bottom down. opened a strake at the turn of bilge inside fore and aft, as per Rule, air courses twin decks. the timbers proved sound. Renewed the two strakes inside with Baltic fir. recaulked the bottom and resheathed it with line on felt, and gave her a general overhaul. —

Present Condition of the

Decks <u>In good order</u>	Treenails <u>good</u>	Windlass and Capstan <u>in good order</u>
Waterways <u>"</u>	Breasthooks and Stemson <u>"</u>	Pumps <u>"</u>
Comings <u>"</u>	Transoms, Pointers, and Crutches <u>"</u>	Boats <u>"</u>
Upper Deck Beams & Fastenings <u>"</u>	Timbers of the Frame <u>"</u>	Masts, Yards, &c. <u>"</u>
Lower Deck Beams & Fastenings <u>"</u>	Keelsons <u>"</u>	Sails <u>"</u>
Planksheers <u>"</u>	Clamps and Shelves <u>"</u>	Anchors No. of <u>3</u> <u>"</u>
Sheerstrakes <u>"</u>	Ceiling <u>now hooped at upper part</u> <u>"</u>	Cables <u>"</u>
Topsides <u>"</u>	Rudder <u>efficient</u> <u>"</u>	Hawsers and Warps <u>"</u>
Wales <u>"</u>	<u>Copper</u> <u>Line on felt</u> <u>When put on - 1859.</u> <u>"</u>	Standing & Running Rigging <u>"</u>
Plank (Bottom) and Counter <u>"</u>		

General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways. now good.

Examined her outside and inside. Decks, waterways, Comings, head ledges. Ribs, timbers, Sparre where seen. Her general appearance sheer &c proving all good and efficient. I am of opinion she is fit for the conveyance of dry and perishable cargoes and eligible to receive Clap's A. 1.

Change of Owners X
 The Amount of Fee £ 1 : - : - is received by me,

Special 2 : 2 : -

Certificate (X required) - : 5 : -

Committee's Minute 11th November 1859

Character assigned B. 1

S. 1. 57 - 4 years



© 2019

Lloyd's Register
Foundation

LONG 41-0412