

REPORT of SURVEY for REPAIRS.

22889

No. 225 on the *St. Mary's* Master *London* Date *11th 14th Jan 1860*

Tonnage *393* Built at *Sunderland* When built *1858*

By whom built *Caran Co.* Owners *Caran Co.*

Port belonging to *London* Destined Voyage *London & West Indies*

If Surveyed Afloat or in Dry Dock *Afloat West India Imp'd Co*

Last Survey, No. *22839* Port *London* Classed *13 AS*

REPAIRS of Damage caused by collision with the *Bt Patricia* in the *spoons*

On the Starboard side, two rough tree stentions removed of English Oak. two lengths of Sheerstrake from Foremast to shaft. The main mast & one midship length of plank sheers removed with teats. original waterway bolts clenched on the timbers and other bolts put through sheerstrake & waterway in the range of the damage. Lodging knees rebolted. Fore & main channels & chain bolts renewed also the main rails and berthing.

Caulked from metal line up to the third seam of deck on each side.

Present Condition of the

Decks <i>Good</i>	Treenails <i>Good where seen</i>	Windlass and Capstan <i>Good</i>
Waterways <i>"</i>	Breasthooks and Stemson <i>Not seen for Cans</i>	Pumps <i>"</i>
Comings <i>"</i>	Transoms, Pointers, and Crutches <i>"</i>	Boats <i>one seen</i>
Upper Deck Beams & Fastenings <i>new</i>	Timbers of the Frame <i>"</i>	Masts, Yards, &c. <i>"</i>
Lower Deck Beams & Fastenings <i>Good</i>	Keelsons <i>"</i>	Sails <i>"</i>
Plank sheers <i>one length new</i>	Clamps and Shelves <i>"</i>	Anchors No. of <i>sufficient</i>
Sheerstrakes <i>two lengths new</i>	Ceiling <i>"</i>	Cables <i>"</i>
Topsides <i>Caulked</i>	Rudder <i>Good</i>	Hawsers and Warps <i>"</i>
Wales <i>"</i>	Copper <i>When put on</i>	Standing & Running Rigging <i>"</i>
Plank (Bottom) and Counter <i>Good</i>		

General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways. *Good where tried*

This vessel is now in good and efficient condition eligible to remain as classed 13 AS

The Amount of Fee.....£ / : : is received by me,

Special..... : : :

Certificate (if required) : 5 : -

Committee's Minute *31st January 1860*

Character assigned *13 AS*

record damage repair



© 2019

Lloyd's Register Foundation

LON 642-0109