

229 14

# REPORT of SURVEY for REPAIRS.

Continuation

No. 61 Survey held at London Date Nov<sup>r</sup> 3<sup>rd</sup> to Dec<sup>r</sup> 7<sup>th</sup> 1859  
on the Barge "Neilly" Master J. Orfew  
Tonnage 219 Built at New Brunswick When built 1833  
By whom built \_\_\_\_\_ Owners Thompson & Brodie  
Port belonging to London Destined Voyage New Zealand  
Surveyed Afloat and in Dry Dock Princes Dock

Recd 11/12/59

Last Survey, No. 180 Port St. John Classed 4 A 1

REPAIRS Now done according to the Rules, Section 54 and 63. The keel scraped bright extending from the light water mark to the waterway seams, trenails and bolts driven out for survey, a strake of plank taken out each side at the bilge inside, and a strake split out each side in the topsides - timbers examined and found satisfactory. She has been caulked from the keel to the waterways, and the upper deck, her main beam of Rudder renewed with English Oak, and her bottom resheathed with Yellow Metal on Telt.

The upper deck and Comings, the upper and lower deck bolts and the planks thro' which they pass, the whole of the planking inside and outside, the beams, keel, keelson, all the frame timbers, stem, stern post, Rudder and windlass, and other parts of the vessel were seen found to be in good condition. Her stern and gun remain unaltered.

Present Condition of the

Decks <u>Caulked</u>	Treenails _____	Windlass and Capstan _____
Waterways <u>scraped &amp; Caulked</u>	Breasthooks and Stenson _____	Pumps _____
Comings <u>good</u>	Transoms, Pointers, and Crutches _____	Boats _____
Upper Deck Beams & Fastenings _____	Timbers of the Frame _____	Masts, Yards, &c. _____
Lower Deck Beams & Fastenings <u>good</u>	Keelsons <u>good when seen</u>	Sails <u>Good and</u>
Planksheers _____	Clamps and Shelves _____	Anchors No. of <u>suff<sup>t</sup></u>
Sheerstrakes <u>scraped and</u>	Ceiling _____	Cables _____
Topsides <u>caulked</u>	Rudder <u>Yellow Metal</u>	Hawsers and Warps _____
Vales _____	<u>Copper on Telt</u> When put on <u>now</u>	Standing & Running Rigging _____
Plank (Bottom) and Counter <u>Caulked</u>		

General Observations and Opinion, Caulking of Bottom, Deck, & Waterways. Good when tested  
The Rules, Section 54 and 63 have been complied with - we are of opinion that she is fit to be continued for 2 years A. 1. from 1859 and marked in the Registry Book S.S. for 4 years - and beg to submit her claims to the Committee accordingly.

The Amount of Fee.....£ 3 : - : - is received by me,  
Special..... 3 : 3 : -  
Certificate (if required) : : -

W. Maymounth  
Samuel Retway.

Committee's Minute 10<sup>th</sup> February 1860

Character assigned Cont<sup>d</sup> for 2 Years from 1859  
S.S. 59 = 4 Years