

# REPORT of SURVEY for REPAIRS.

No. 136 Survey held at London Date Apr 25 to May 8 1860  
 on the Ship Orient Master Lawrence  
 Tonnage 1133 Built at London When built 1833  
 By whom built Sup<sup>r</sup> J. Bilbe & Co Owners Sup<sup>r</sup> J. Thomson & Co  
 Port belonging to London Destined Voyage Adelaide  
 If Surveyed Afloat or in Dry Dock Nelson Dry Dock

Last Survey, No. 22394 Port London Classed S.A. 1.

REPAIRS Now done, the ship hung in shores and Caulked from the keel to the Gunwale and nearly the whole of the upper deck, her bottom sheathed with Yellow Metal on Felt - 106 feet running, of main deck waterway each side in the waist renewed, in one length, each side and an inner waterway 9 x 12 introduced each side in three lengths with Pugit Sound Pine - let down about 2 over the upper deck beams - the Inner Waterway bolted with 1 1/2 Yellow Metal bolts in every other timber, and the Inner waterway with 1 1/2 Yellow Metal thi' bolts spaced about 4.6 apart, both Waterways bolted to the beams with two Galvanized Iron bolts in each beam end; one upper deck beam end each side scarphed with Pugit Sound Pine P.F. O

## Present Condition of the

Decks <u>Caulked</u>	Treenails	Windlass and Capstan
Waterways <u>Caulked &amp; F<sup>r</sup> new</u>	Breasthooks and Stenson	Pumps
Comings <u>Good</u>	Transoms, Pointers, and Crutches	Boats
Upper Deck Beams & Fastenings	Timbers of the Frame <u>Good where</u>	Masts, Yards, &c. <u>Good and</u>
Lower Deck Beams & Fastenings <u>Good</u>	Keelsons <u>seen</u>	Sails <u>Suff<sup>t</sup></u>
Planksheers	Clamps and Shelves	Anchors No. of
Sheerstrakes <u>Caulked</u>	Ceiling	Cables
Topsides	Radder	Hawsers and Warps
Wales	Copper on Felt When put on <u>Iron</u>	Standing & Running Rigging
Plank (Bottom) and Counter <u>Caulked</u>		

## General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways. Good where tested -

She is now fit in my opinion to remain as classed  
S.A. 1.

B. Wapmouth

The Amount of Fee.....£ 3 : - : is received by me,


Special..... / : / :

Certificate (if required) : :

Committee's Minute 1<sup>st</sup> June 1860

Character assigned S.A. 1

second repairs



© 2019

Lloyd's Register Foundation

LON 642-0404



