

REPORT of SURVEY for REPAIRS.

23244

No. 185 on the S. "Mermaid" Survey held at London Date 4th to 21st June 1860
 Master J. White
 Tonnage 1321 Built at St Johns When built 1853
1233
 By whom built _____ Owners Wilson &
 Port belonging to Liverpool Destined Voyage Melbourne
 If Surveyed Afloat or in Dry Dock Repⁿ Wyman's dry dock

Last Survey, No. 15814 Port London Classed Y A1

REPAIRS

At present specially surveyed for Continuation in accordance with Rules Section 54 & 63. Yellow metal and wood sheathing entirely stripped off, outside planking brightened from light water live upwards including Plank sheers and Waterways, bolts and Treennails driven out for inspection and found good and a stroke of plank inside at upper part of bulges all fore and aft on each side removed, the frame there examined & found good, one new plank of Wales on the Starb^d side of Pitch pine, one upper deck Beam forward new of Pitch Pine, new Windlass of E & S Oak, recaulked from keel to thick beam of deck next the Waterways, upper courses of bottom & part of the Wales sheathed with Yellow Pine over feet fastened with Composite iron and galvanised iron nails and the bottom re-sheathed with Yellow metal on felt, Treennails under wood sheathing in number equal to the requirements of Rule Sec 66 now driven out for inspection.

Present Condition of the	new	inspected
Decks <u>Good</u>	Treennails <u>Good</u>	Windlass and Capstan <u>Good</u>
Waterways <u>do</u>	Breasthooks and Stemson <u>do</u>	Pumps <u>4 ho</u> <u>do</u>
Comings <u>do</u>	Transoms, Pointers, and Crutches <u>do</u>	Boats <u>5 ho</u> <u>do</u>
Upper Deck Beams & Fastenings <u>do</u>	Timbers of the Frame <u>do</u>	Masts, Yards, &c. <u>do</u>
Lower Deck Beams & Fastenings <u>do</u>	Keelsons <u>do</u>	Sails <u>do</u>
Plank sheers <u>do</u>	Clamps and Shelves <u>do</u>	Anchors No. of <u>3 B. 1 S & 2 K</u>
Sheerstrakes <u>do</u>	Ceiling <u>do</u>	Cables <u>300 fms - 4 Ashman chain</u>
Topsides <u>do</u>	Rudder <u>do</u>	Hawsers and Warps (new) <u>3 ho</u>
Wales <u>part sheathed on feet - do</u>	Copper <u>1 lb on feet</u> When put on _____	Standing & Running Rigging <u>do</u>
Plank (Bottom) and Counter <u>do - do</u>		

General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways. Good where tested

This Vessel having been specially surveyed as above and now being in a good and efficient condition for the safe conveyance of dry and perishable cargoes to and from all parts of the world we are of opinion she is eligible to be continued A1 for 2 years at the expiration of her present Character.

The Amount of Fee.....£ 5 : - is received by me,

Special..... 3 : 3 : -

Certificate (if required) : 5 : -

Committee's Minute 3rd July 1860

Character assigned Cont^d 1 for 2 Years

J. M. Mackay & Co
2 Monyate St

S.S. 60 - 5 days
record repair

© 2019

Lloyd's Register
Foundation

200643-0014