

REPORT of SURVEY for REPAIRS.

For Continuation

Nov 21/60

No. Survey held at London Date 25th Aug & 17th July 1860
on the Ship Lady Macdonald Master H. Brindle
Tonnage 578 Built at Montreuil When built 1847
By whom built Owners S. Penbar
Port belonging to London Destined Voyage for China
If Surveyed Afloat or in Dry Dock Ships dry dock
Last Survey, No. 21403 Port London Classed 12 D Lapsed

REPAIRS

Now done in accordance with the rules Sec 54.
The yellow metal and wood sheathing stripped off the bottom, the vessel scraped and scrubbed bright from light. Water marks upwards including plank sheers and waterways. Iron bolts driven out and the Quirls stripped and overhauled, all in strict accordance with the rules Sec 54.
The rivet bolts of lower deck knees and the bolts in six strakes at the bilges on each side driven out and renewed. Bolts in other parts of the bottom taken out and found satisfactory. The vessel caulked from keel to plank sheers. The bottom resheathed with good over felt and re-nailed.

Present Condition of the		
Decks <u>Good</u>	Treenails <u>None - bolts put in</u>	Windlass and Capstan <u>Good</u>
Waterways <u> </u>	Breasthooks and Stenson <u>Good</u>	Pumps <u> </u>
Comings <u> </u>	Transoms, Pointers, and Crutches <u> </u>	Boats <u> </u>
Upper Deck Beams & Fastenings <u> </u>	Timbers of the Frame <u> </u>	Masts, Yards, &c. <u> </u>
Lower Deck Beams & Fastenings <u> </u>	Keelsons <u> </u>	Sails <u> </u>
Plank sheers <u> </u>	Clamps and Shelves <u> </u>	Anchors No. of <u>3 B. 1 S. 2 K</u>
Sheerstrakes <u> </u>	Ceiling <u> </u>	Cables <u>Sufficient</u>
Topsides <u> </u>	Rudder <u> </u>	Hawsers and Warps <u> </u>
Wales <u> </u>	Copper <u> </u> When put on <u>Good</u>	Standing & Running Rigging <u> </u>
Plank (Bottom) and Counter <u> </u>		

General Observations and Opinion, Caulking of Bottom, Deck, & Waterways. Good where tried

This ship is now in good and efficient condition and having undergone the whole of the requirements of the rules Sec 54 is eligible in our opinion to be continued for four years from 1859 on the A S Character.

The Amount of Fee.....£ 3 : : is received by me,

Special..... 3 : 3 : :

Certificate (if required) : 5 : :

Committee's Minute 28th August 1860

Character assigned Cowp for 4 years from 1859

W. Mumford
Thos. W. Stawn