

REPORT of SURVEY for REPAIRS.

and change of owners

No. 57 Survey held at London Date 8th Aug to 27th Sept 1860
on the Scpr "Maid of Adu" Master

Tonnage 133 Built at Aberdeen When built 1841

By whom built _____ Owner J. Sweet

Port belonging to London Destined Voyage _____

If Surveyed Afloat or in Dry Dock Ratcliffe Cross dry dock & London docks

Last Survey, No. 21583 Port London Classed 9 1
C 3 37

REPAIRS

Defective main and Rider keelsons removed and replaced with a new main keelson of Pitch Pine 11¹/₂ ins side 15¹/₂ ins moulded. two stons aft and some chocks to heels of after caulk renewed with American Elm. After planks of lumber strakes on each side. two planks next the lumber strake on the starb^d side and three on the port side aft renewed with Swedish Fir. 2 fore hoods of starb^d bilge strakes & one short piece on the port side of Swedish Fir. five planks of ceiling above bilges on the starb^d side and 3 on the port side new of Pitch Pine and Swedish Fir. some defective treenails driven out and renewed. lower Breast hook renewed with Iron - part new main hatchway coming caulked from keel to light water line. Re & main mast topmasts at keel 15 fms chain cables & a 6 in Hemp stowser provided to make good deficiencies

Present Condition of the

| | | | | | | |
|-------------------------------|-------|----------------------------------|-------------|----------------------------|-----------------------|----------|
| Decks | Good | Treenails | part new | Windlass and Capstan | with R.P. which | Good |
| Waterways | do | Breasthooks and Stenson | Good | Pumps | 2 of Iron | do |
| Comings | | Transoms, Pointers, and Crutches | where | Boats | one | do |
| Upper Deck Beams & Fastenings | Good | Timbers of the Frame | seen | Masts, Yards, &c. | | good |
| Lower Deck Beams & Fastenings | | Keelsons | new | Sails | | do |
| Plank sheers | where | Clamps and Shelves | | Anchor | No. of 2 B. 1 S & 1 H | |
| Sheerstrakes | | Ceiling | part new | Cables | 15 fms new | complete |
| Topsides | | Rudder | None | Hawsers and Warps | one new | do |
| Wales | | Copper | When put on | Standing & Running Rigging | | do |
| Plank (Bottom) and Counter | seen | | | | | |

General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways.

Good where seen
This Vessel is at present in good condition fit for the safe conveyance of dry cargoes and in my opinion eligible to be classed A.1

The Amount of Fee.....£ : 10 : - is received by me,

Special.....2 : 2 : -

Certificate (X required) : 2 : 6

Committee's Minute 28 September 1860

Character assigned A.1

second repair



© 2019

Lloyd's Register Foundation

lon 643-0210