

23517

Recd 29. 10. 60

Continuation

# REPORT of SURVEY for REPAIRS.

No. 20 Survey held at London Date October 3<sup>rd</sup> 1860  
 on the Ship "Abyssinian" Master W. Punchard  
 Tonnage 1140 Built at New Brunswick When built 1834  
 By whom built \_\_\_\_\_ Owners Thos Beech & Co  
 Port belonging to London Destined Voyage Gottingburg  
 If Surveyed Afloat or in Dry Dock Clyde Dry Dock

Last Survey, No. 22448 Port of London Classed 1st

REPAIRS Now done, according to the Rules Sections 54 and 53, her sides scraped bright extending from the yellow metal sheathing to the waterway beam, trenails and bolts driven out for survey, the windlass stepped and examined, and a stroke of plank taken out each side fore and aft at the bilges inside, timbers examined and found good - Vouchers have been produced showing that her bottom was sheathed with yellow metal on 1<sup>st</sup> Feb at Bombay in March 1860 - A few trenails which proved slack have been renewed in the topsides - She has been caulked from the yellow metal sheathing to the gunwale - The upper deck and Comings, the whole of the bolts and trenails, the planking, timbers, and all the component parts of the ship are in good Condition - Her form remains unaltered -

Decks	Trenails	Windlass and Capstan
Waterways } <u>Good</u>	Breasthooks and Stemson	Pumps
Comings }	Transoms, Pointers, and Crutches	Boats
Upper Deck Beams & Fastenings	Timbers of the Frame } <u>Good where seen</u>	Masts, Yards, &c. } <u>Good and suff<sup>ce</sup></u>
Lower Deck Beams & Fastenings } <u>Good</u>	Keelsons }	Sails
Plank sheers	Clamps and Shelves	Anchors No. of
Sheerstrakes } <u>Scraped and</u>	Ceiling	Cables
Topsides } <u>Caulked</u>	Rudder	Hawsers and Warps
Wales	<u>Yellow metal</u>	Standing & Running Rigging
Plank (Bottom) and Counter	Copper on 1 <sup>st</sup> Feb When put on <u>1860</u>	

General Observations and Opinion, Caulking of Bottom, Deck, & Waterways. Good where tested -  
The Rules Section 54 & 53 have been complied with.  
She is in good and efficient Condition fit in our opinion to be continued for 2 years 1<sup>st</sup> from 1860 and to be marked S.S. in the Register Book for 3 years.

The Amount of Fee.....£ 5 : - is received by me.

Special.....5 : 5 : -

Certificate (if required) : -

Committee's Minute 30<sup>th</sup> October 1860

Character assigned Cont for 1 yr 2 years  
S.S. 40 & 5 years  
Record 9/11



© 2019

Lloyd's Register Foundation

LOV 643-0268