

23549.

Damage &c  
**REPORT of SURVEY for REPAIRS.**

Rec 13/11/60

No. 130 Survey held at London Date Oct<sup>r</sup> 30 1860  
on the Ship "Harwich" Master Geo Franklin  
Tonnage 613 Built at Harwich When built 1837  
By whom built \_\_\_\_\_ Owners Messrs Bonus &  
Port belonging to London Destined Voyage \_\_\_\_\_  
If Surveyed Afloat or in Dry Dock Messrs Fletchers Dry Dock

Last Survey, No. 21053 Port London Classed G.F. 1.

REPAIRS for damage - The whole of the main keel, the lower part of the Rudder and the lower part of the false Stern Post; renewed, also the Garboard strakes both sides and a listing of the bottom plank adjoining them, with English and American Elm. The vessel hung in shivers and the yellow metal sheathing stripped off extending from the keel to the stem heads, the seams of bottom thus exposed, Caulked; the yellow metal sheathing referred to renewed on felt.

The following repairs not consequent on damage - viz - Two shifts of bottom on the larboard side aft, one shift in the run, and two starboard shifts of bottom plank forward renewed with Elm - A <sup>new</sup> false keel added, the vessel Caulked P.F.O

Present Condition of the

Decks	Treenails	Windlass and Capstan
Waterways } <u>Good where</u>	Breasthooks and Stems	Pumps
Comings } <u>seen</u>	Transoms, Pointers, and Crutches	Boats
Upper Deck Beams & Fastenings	Timbers of the Frame	Masts, Yards, &c. } <u>Good and</u>
Lower Deck Beams & Fastenings } <u>firm</u>	Keelsons	Sails } <u>sufficient</u>
Planksheers	Clamps and Shelves } <u>seen</u>	Anchors No. of
Sheerstrakes } <u>Caulked</u>	Ceiling	Cables
Topsides	Rudder	Hawsers and Warps
Wales	<u>Yellow Metal</u>	Standing & Running Rigging
Plank (Bottom) and Counter <u>Caulked</u>	<u>Copper on Felt</u> When put on <u>now</u>	

General Observations and Opinion, Caulking of Bottom, Deck, & Waterways. Good where tested -  
She has been put into good and efficient Condition  
and is now fit in my opinion to remain as classed -  
G.F. 1.

The Amount of Fee.....£ / : - : - is received by me,

Special..... / : / : -

Certificate (if required) : ~~1~~ -

Committee's Minute 13<sup>th</sup> November 1860

Character assigned G.F. 1 - record damage repair  
Damage Fee £44.0



23549 Don

from the Shore heads to the Gunwale, and the  
Yellow Metal sheathing extending from the shores  
to the Yellow Metal sheathing line, renewed on  
Selt - three Rudder Braces taken off and refitted  
and bolted -

B. Weymouth



© 2019

Lloyd's Register  
Foundation