

REPORT of SURVEY for REPAIRS.

No. 20 Survey held at London Date Feb^r 2nd to 14th 1861
 on the Ship "Undaunted" Master J. C. Clare
 Tonnage 1245 Built at Sunderland When built 1837
 By whom built _____ Owners J. Fleming &
 Port belonging to London Destined Voyage India
 If Surveyed Afloat or in Dry Dock Dry Dock

Last Survey, No. 23116 Port London Classed 13A.1.

REPAIRS Now done an inner waterway introduced to the upper
deck of Green Heart 12 x 14 let down 2 over the beams, and
extending lengthwise from about twenty feet abaft the
break, to a good shift before the Forecastle
break, well battened with Yellow Metal thro' bolts -
in addition to which she has a large number of 1 1/8
Yellow Metal thro' bolts driven thro' her upper and
lower deck shelves, and about 500 addition trenails
driven in her topsides, her after Hatch in the upper
deck shifted forward, and the deck Planks renewed
where required by this alteration, and by the
introduction of the waterway - She has been thoroughly
Caulked from Keel to Gunwale and a portion of the
upper deck, her butto and wood ends of bottom lead listed
And the bottom resheathed with G. M. or Sell-

Decks <u>part new pt Caulked</u>	Treenails	Windlass and Capstan
Waterways <u>good, Caulked</u>	Breasthooks and Stemson	Pumps
Comings <u>good</u>	Transoms, Pointers, and Crutches	Boats
Upper Deck Beams & Fastenings	Timbers of the Frame <u>Good where</u>	Masts, Yards, &c. <u>Good and</u>
Lower Deck Beams & Fastenings <u>good</u>	Keelsons <u>seen</u>	Sails <u>suff.</u>
Planksheers	Clamps and Shelves	Anchors No. of
Sheerstrakes <u>Caulked</u>	Ceiling	Cables
Topsides	Rudder <u>Yellow Metal</u>	Hawsers and Warps
Wales	Copper <u>or Telt</u> When put on <u>now</u>	Standing & Running Rigging
Plank (Bottom) and Counter <u>Caulked</u>		

General Observations and Opinion, Caulking of Bottom, Deck, & Waterways. Good where tested
She has now been put in to good and efficient
Condition, is fit in my opinion to remain as
Classed 13A.1.

The Amount of Fee.....£ 3 : - : - is received by me,
 Special.....£ 2 : 2 : -
 Certificate (if required) : 5 :

Committee's Minute 1st March 1861
 Character assigned 13A.1



© 2021
 Lloyd's Register
 Foundation
 LON644-0031