

23742

REPORT of SURVEY for REPAIRS.

Change of Owners _____ and _____ Mid Term Survey
No. _____ Survey held at London Date Nov. 6th 1861
on the Ship 'Chrysolite' Master Roy
Tonnage 364 Built at Aberdeen When built 1858
By whom built _____ Owners Wardley, Comp. & Co
Port belonging to Liverpool Destined Voyage to China
If Surveyed Afloat or in Dry Dock Twice dry dock

Recd 12/12/61

Last Survey, No. 21468 Port London Classed 14A1

REPAIRS now done

Defective greenheart keelson, removed & replaced aft and the keelson bolts cut off and clenched on the floors the keelson renewed with oak and bolted with yellow metal through the floor (double) floors and through the false keel. The ship run in shores. The yellow metal sheathing (except the four upper strakes) stripped and the bottom caulked from stern to keel and resheathed with yellow metal on paper. Two planks of ceiling of hold (one on each side aft) removed & rebolted.

Present Condition of the

Decks <u>Good</u>	Treenails <u>Good where seen</u>	Windlass and Capstan _____
Waterways _____	Breasthooks and Stenson _____	Pumps <u>Good and</u>
Comings _____	Transoms, Pointers, and Crutches _____	Boats _____
Upper Deck Beams & Fastenings _____	Timbers of the Frame _____	Masts, Yards, &c. <u>Efficient</u>
Lower Deck Beams & Fastenings _____	Keelsons <u>new</u>	Sails _____
Planksheers _____	Clamps and Shelves <u>Good where seen</u>	Anchors No. of <u>where</u>
Sheerstrakes _____	Ceiling <u>part new & repaired</u>	Cables _____
Topsides _____	Rudder <u>Good</u>	Hawsers and Warps <u>seen</u>
Wales _____	Copper <u>part new & repaired</u>	Standing & Running Rigging _____
Plank (Bottom) and Counter _____	When put on <u>new & on paper</u>	

General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways. Good where tried

This vessel is now in good and efficient condition eligible to remain as classed 14A1

The Amount of Fee £ 1 : - : - is received by me, W. M. Munro
Renewed application with Special..... 2 : 2 : - Paid at Liverpool
Certificate (if required) : 5 : - Vide Letter 23/11/61 Thos. W. Wain

Committee's Minute 5th March 1861

Character assigned 14A1

Record repair



© 2021
Lloyd's Register
Foundation
LON644-0038