

23782

# REPORT of SURVEY for REPAIRS.

Recd 18.3.61

No. \_\_\_\_\_ Survey held at London Date 13<sup>th</sup> Feb to 10<sup>th</sup> March 1861  
on the Ship Bertrude Master T Speedling  
Tonnage 948 Built at Shields When built 1856  
By whom built \_\_\_\_\_ Owners D Drumbar  
Port belonging to London Destined Voyage Lon  
If Surveyed Afloat or in Dry Dock Canal dry dock

Last Survey, No. 22073 Port London Classed 13 A 1  
REPAIRS now done 50

New forepiece of keelson, and chock before the foremast floor of oak - the 4 in sheathing stripped off the bottom the ship turned in shores and caulked from keel beam, to plank sheer, and the bottom resheathed with 4 in. on felt.

Eight planks of deck on each side forward renewed and the rest of the deck remained. Windlass stripped and the bolts renewed on the port side the sole pieces under the flukes of the windlass bits renewed. The decks caulked and two pairs of iron hanging knees added to lower deck beams.

## Present Condition of the

Decks <u>Good</u>	Treenails <u>Good where seen</u>	Windlass and Capstan <u>Good</u>
Waterways <u>"</u>	Breasthooks and Stemson <u>"</u>	Pumps <u>"</u>
Comings <u>"</u>	Transoms, Pointers, and Crutches <u>"</u>	Boats <u>Good</u>
Upper Deck Beams & Fastenings <u>"</u>	Timbers of the Frame <u>"</u>	Masts, Yards, &c. <u>New Main Mizzen</u>
Lower Deck Beams & Fastenings <u>"</u>	Keelsons <u>forepiece new</u>	Sails <u>Sufficient</u>
Plank sheers <u>"</u>	Clamps and Shelves <u>Good</u>	Anchors No. of <u>"</u>
Sheerstrakes <u>"</u>	Ceiling <u>"</u>	Cables <u>(where)</u>
Topsides <u>"</u>	Rudder <u>"</u>	Hawsers and Warps <u>"</u>
Wales <u>"</u>	Copper <u>on felt</u> When put on <u>how close</u>	Standing & Running Rigging <u>seen</u>
Plank (Bottom) and Counter <u>"</u>		

General Observations and Opinion, Caulking of Bottom, Deck, & Waterways. Good where true

This ship is in good and efficient condition eligible to remain as classed 13 A 1

The Amount of Fee.....£ : : is received by me,  
Special..... 1 : 1 :  
Certificate (if required) : :

*T. Mumford*  
*W. Light*

Committee's Minute 22<sup>nd</sup> March 1861

Character assigned 13 A 1 *renewed*

