

REPORT of SURVEY for REPAIRS.

23841

No. 898 Survey held at London Date 11th Feb to 14th April 18 61
on the S^r "Crystal Palace" Master See Entry out
Tonnage 494 Built at Seignmouth When built 1852
By whom built _____ Owners J. Lidgett
Port belonging to London Destined Voyage _____
If Surveyed Afloat or in Dry Dock Afloat St Katharines Dock

Last Survey, No. 20272 Port London Classed 11A1

REPAIRS

In consequence of damage, two midship planks of sheerstrake on port side renewed with Teak and one rough tree with Eng: Oak - Decay:

Three planks of lower hold ceiling renewed and the ceiling repaired by piecing, one strake of deck next waterway on each side and one plank on port side renewed and the deck additionally fastened - Sheerstrake of raised quarter on Port side renewed with Fitch Pine and recaulked from metal line up except raised quarter deck and topgallant fore-castle -

Metal put on at Whampoa.

Present Condition of the

Decks		Treenails		Windlass and Capstan	
Waterways	} good	Breasthooks and Stemson	} good	Pumps	
Comings		Transoms, Pointers, and Crutches		Boats	
Upper Deck Beams & Fastenings	} good	Timbers of the Frame	} where seen	Masts, Yards, &c.	} Good
Lower Deck Beams & Fastenings		Keelsons		Sails	
Planksheers	} where seen	Clamps and Shelves	} do	Anchors No. of	} sufficient
Sheerstrakes		Ceiling		Cables	
Topsides	do	Rudder	do	Hawsers and Warps	
Wales	do	Copper <u>Y.M.</u> When put on <u>Sep. 1860</u>		Standing & Running Rigging	
Plank (Bottom) and Counter	do				

General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways. good where tested

This vessel is now in good condition and is eligible in my opinion to remain classed A1

The Amount of Fee.....£ 1 : : is received by me,

Special..... 3 : 3 :

Certificate (if required) : :

Committee's Minute 16th April 18 61

Character assigned 11A1 record damage repair



© 2021

Lloyd's Register Foundation

LONG44-0125