

# 23896 Damage **REPORT of SURVEY for REPAIRS.**

No. 468 Survey held at London Date March 4<sup>th</sup> 1861  
 on the Barge "Puckers" Master M<sup>r</sup> Cummings  
 Tonnage 329 Built at London When built 1829  
 By whom built 39<sup>th</sup> Owners Ships<sup>co</sup> Scrutton  
 Port belonging to London Destined Voyage \_\_\_\_\_  
 If Surveyed Afloat or in Dry Dock Union Dry Dock -

Last Survey, No. 22549 Port London Classed 2<sup>nd</sup> A<sup>1</sup>

REPAIRS Now done, the yellow metal sheathing stripped and renewed extending from the keel to the upper turn of the bilge, the keel being in shores and caulked from the keel to the upper turn of the bilge and from the sixth seam down of topsides to the second seam of deck inside the waterway, and the butts of the deck - ten Roughtree stantions renewed with English Oak, three lengths of Roughtree Oak, and all the bulwarks renewed - the Quarter Braces taken down and refitted, and the Stern Caulked - two fore most lengths of false keel renewed -

## Present Condition of the

Decks	Treenails	Windlass and Capstan
Waterways } <u>Good, Caulked</u>	Breasthooks and Stems	Pumps
Comings }	Transoms, Pointers and Crutches	Boats
Upper Deck Beams & Fastenings } <u>Good</u>	Timbers of the Frame	Masts, Yards, &c. } <u>Good and efficient</u>
Lower Deck Beams & Fastenings }	Keelsons	Sails
Planksheers }	Clamps and Shelves	Anchors No. of
Sheerstrakes } <u>Caulked</u>	Ceiling	Cables
Topsides }	Budder	Hawsers and Warps
Wales } <u>Good</u>	<u>Yellow metal 1839 and built</u>	Standing & Running Rigging
Plank (Bottom) and Counter } <u>Part-Caulked</u>	Copper Tell. When put on <u>Now</u>	

## General Observations and Opinion,

## Caulking of Bottom, Deck, & Waterways.

Good where tested.  
 The ship is now in good and efficient condition. It is in my opinion for the safe conveyance of dry and perishable cargoes to and from all parts of the world and to be in classed \*A<sup>1</sup> Asterisk B.

The Amount of Fee.....£ 1 : - : is received by me, M. W. Maymouth

Special..... : : W

Certificate (if required) : :

Committee's Minute 26<sup>th</sup> April 1861

Character assigned \*A<sup>1</sup> Asterisk B

Damage Fee £ 3 .. 3 .. 0



© 2021

Lloyd's Register Foundation