

24068

REPORT of SURVEY for REPAIRS.

Continuation

No. 263 on the *4 1/2* "Sigris" Survey held at *London* Date *July 24th* 18 *61*
Master *Pawley*
Tonnage *399* Built at *Sunderland* When built *1857*
By whom built _____ Owners *W Smith & Co*
Port belonging to *London* *Scarb* Destined Voyage _____
If Surveyed Afloat or in Dry Dock *New Crane dry dock*

Rec'd S. S. Co

Last Survey, No. *21841* Port *London* Classed *9 A 1* *uprd*
58

REPAIRS

The yellow metal sheathing stripped off, the outside plank-
ing from the light water mark to the waterway seam
scraped bright and treenails and bolts driven out for inspection.
One plank of sheerstrake on starboard, one plank of wales
on port bow and one topside plank on each quarter new
of Eng: Oak - Throat and lug bolts of lower deck knees
renewed with yellow metal, Retreenailed from light mark
to planksheers with Eng: Oak; Windlass, Main piece of
rudder and scuttle hatch comings renewed with Eng: Oak.
Three (broken) Iron hooks repaired refitted and bolted and
a stemson added of E. I. Teak - Recaulked from keel to
waterway seam and resheathed with yellow metal on
Felt

Present Condition of the

Decks	} <i>Good</i>	Treenails <i>pt new, new</i>	} <i>good</i>	Windlass and Capstan	<i>new</i> <i>good</i>
Waterways		Breasthooks and Stemson		Pumps	<i>2 of Iron</i>
Comings		Transoms, Pointers, and Crutches	<i>do</i>	Boats	<i>3</i>
Upper Deck Beams & Fastenings	} <i>do</i>	Timbers of the Frame	<i>do</i>	Masts, Yards, &c.	} <i>sufficient</i>
Lower Deck Beams & Fastenings		Keelsons	<i>do</i>	Sails	
Planksheers	} <i>where seen</i>	Clamps and Shelves	<i>do</i>	Anchors No. of	<i>3 X 1 X 2</i>
Sheerstrakes		Ceiling	<i>do</i>	Cables	<i>240 fms</i>
Topsides	<i>do</i>	Rudder	<i>do</i>	Hawsers and Warps	} <i>sufficient</i>
Wales	<i>do</i>	Copper <i>T. L. Y. M.</i> When put on	<i>now</i>	Standing & Running Rigging	
Plank (Bottom) and Counter	<i>do</i>				

General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways. *good where tested*

This vessel has now been Specially Surveyed in
accordance with the Rules Sec: 54. She is now in a good
and efficient state of repair and is eligible in our opinion
to be continued

The Amount of Fee.....£ *4* : - : is received by me, *3 A 1*

Special..... *4* : *4* :
Certificate (if required) : *3* : -

Thos. W. Mawson

Committee's Minute *26th July* 18 *61*

Character assigned *Coast. A. 1 for 3 years from 1860*

Record Repair



LON644-0317