

24100

REPORT of SURVEY for REPAIRS.

No. 415 Survey held at London Date July 10th 18 61
on the "Guadalete" Master B W Adamson
Tonnage 275 Built at Wells When built 1854
By whom built Syrell Owners W H Frost
Port belonging to London Destined Voyage Constantinople
If Surveyed Afloat or in Dry Dock Gun dry dock

Recd 13/8/61

Last Survey, No. 23921 Port London Classed 8 A 1
61.

REPAIRS

In consequence of Damage see Special Report.

Yellow metal sheathing stripped off, on Starb^d side, four first futtocks, twenty one Chocks, and two cross chocks under keelson renewed with English Oak, Twelve ceiling planks renewed with English & Rantzie Oak, retreenailed in way of Starb^d fore rigging, bilge and keelson bolts between fore and main masts renewed with Copper, the old riders cut off and replaced with seven pairs diagonal 4x1 1/4 in, ship hung in shores and caulked from keel to Plank sheers - Yellow metal renewed on paper.

Decay.

The midship piece of keelson renewed with E. I. Teak -

Present Condition of the

Decks	} Good
Waterways	
Comings	
Upper Deck Beams & Fastenings	} Good
Lower Deck Beams & Fastenings	
Plank sheers	} where seen
Sheerstrakes	
Topsides	do
Wales	do
Plank (Bottom) and Counter	do

Treenails	pt new	} Good	
Breasthooks and Stenson			
Transoms, Pointers, and Crutches	where seen		
Timbers of the Frame		}	
Keelsons	pt new		
Clamps and Shelves	do		
Ceiling	do		
Rudder	do		
Copper	SM	When put on	now

Windlass and Capstan	} In good order and sufficient
Pumps	
Boats	
Masts, Yards, &c.	
Sails	
Anchors No. of	
Cables	
Hawsers and Warps	}
Standing & Running Rigging	

General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways.

good where tested

This vessel is now in good and efficient condition and is eligible in our opinion to remain classed 8 A 1

The Amount of Fee.....£ 10: - is received by me,

Special. ~~charge~~ 3: 3: -

Certificate (if required) - - - - -

Committee's Minute 16th August 18 61

Character assigned 8 A 1

Thos. W. Wain

W. J. M.



© 2021

Lloyd's Register Foundation

LON644-0355