

*24265

REPORT of SURVEY for REPAIRS.

Restoration

No. _____ Survey held at London Date 6th Nov^r 18 61
on the S. "Sir Robert Seppings" Master S. Clarke
Tonnage 606 Built at Moulmein When built 1844
628
By whom built _____ Owners J. Allan
Port belonging to London Destined Voyage _____
If Surveyed Afloat or in Dry Dock Limetkiln dry dock

Last Survey, No. 22485 Port London Classed 12 A 1
Cent St. 4

REPAIRS

This vessel has now been opened as suggested in the following parts, viz: the plank sheer of the waist and forecastle entirely removed and a listing cut out in line with the main plank sheer exposing the frame all fore and aft in that range; a second listing cut out below all fore and aft in way of the lower deck fastenings and a plank removed on each bullock - Inside; the first and fourth openings from the hold beams down have been continued to the ends of the ship the other ^{openings shewn in sketch} extending from foremast to mizen mast. The beam ends have been bored and the frame has been tested in all parts exposed and found good, excepting four rough trees and eleven toptimbers on the port and two rough trees and four toptimbers also one piece of hawse timber on the starboard side which have been renewed with Teak

Present Condition of the

Decks	Treenails	Windlass and Capstan
Waterways	Breasthooks and Stemson	Pumps
Comings	Transoms, Pointers, and Crutches	Boats
Upper Deck Beams & Fastenings	Timbers of the Frame	Masts, Yards, &c.
Lower Deck Beams & Fastenings	Keelsons	Sails
Plank sheers	Clamps and Shelves	Anchors No. of
Sheerstrakes	Ceiling	Cables
Topsides	Rudder	Hawsers and Warps
Wales	Copper	Standing & Running Rigging
Plank (Bottom) and Counter	When put on	

General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways.

The owner proposes to double this vessel with American Elm diagonally below and Teak horizontally aloft and we beg to leave his claims for restoration to the consideration of the Committee

The Amount of Fee.....£ : : is received by me,

Special..... : :

Certificate (if required) : :

Committee's Minute 10th January 1862

Character assigned _____

Thos. W. Wauw

J. C. Martin

J. H. Ritchie

REPORT OF SURVEY OF NEW YORK

Genl Comm: Survey
of New York
Survey as described, considered
superior in this instance
LMS