

REPORT of SURVEY for REPAIRS.

Handwritten signature
Dec. 12. 61

No. 92 on the S. "Canning" Survey held at London Date 7th Dec^r 1861
Tonnage 899 Built at Thoulmeu When built 1854
By whom built _____ Owners Somes Bes^r
Port belonging to London Destined Voyage Calcutta
If Surveyed Afloat or in Dry Dock Somes dry dock & E.I. Dock

Last Survey, No. 22362 Port London Classed 15 A1

REPAIRS

Yellow Metal stripped off. the bottom dubbed bright and the Chumam taken out from all the bolts, to find leak found seven holes on Each side bored through without any fastenings & chumame over. now bolted with Ym. gripe taken down and leak under the same stopped, one fore hood of larboard strake taken out, found ring shaken and replaced with E.I. Leak. broken planks in buttocks examined by the removal of all pieces. one plank there renewed with E.I. Leak pieces there renewed with E.I. Leak and well fastened recaulked from keel to upper part of wales and the bottom resheathed with Ym on felt. Windlass examined by the removal of wood linings and being found good

Decks		Treenails <u>Copper</u>		Windlass and Capstan <u>Good</u>
Waterways) <u>Good</u>	Breasthooks and Stenson) <u>Good</u>	Pumps <u>2 of Iron</u> <u>do</u>
Comings		Transoms, Pointers, and Crutches		Boats <u>4 do</u> <u>do</u>
Upper Deck Beams & Fastenings		Timbers of the Frame		Masts, Yards, &c. <u>do</u>
Lower Deck Beams & Fastenings) <u>where</u>	Keelsons) <u>where</u>	Sails <u>do</u>
Planksheers		Clamps and Shelves		Anchors No. of <u>3 B. 15 & 11</u>
Sheerstrakes		Ceiling		Cables <u>Good</u>
Topsides) <u>seen</u>	Rudder) <u>seen</u>	Hawsers and Warps <u>2 do & 1 do Chain</u>
Wales		Copper <u>Ym on it</u> When put on <u>now done</u>		Standing & Running Rigging <u>Good</u>
Plank (Bottom) and Counter				

General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways.

Good where tested

This ship is now in good condition and in my opinion eligible to continue as Classed A1

Will: C. Davey

The Amount of Fee.....£..... is received by me,

Special Caulked 1: 1: Handwritten mark

Certificate (if required) : :

Committee's Minute 25th December 1861

Character assigned 15 A1 *Handwritten mark*
second Ym



© 2019

Lloyd's Register Foundation