

REPORT of SURVEY for REPAIRS.

& continuation

No. 309 on the *Yth "William + Jane"* Survey held at *London* Date *December 31st* 18 *61* Master *R. Norris*

*A*m - Tonnage *428* Built at *Sunderland* When built *1853*

By whom built _____ Owners *Suart + Simpson*

Port belonging to *London* Destined Voyage *Madras*

If Surveyed Afloat or in Dry Dock *Timehouse dry dock & E. I. Dock*

Last Survey, No. *23526* Port *London* Classed *8 A 1*
10.60

REPAIRS
At the present time under Special Survey Rule Sec 54. the yellow metal sheathing stripped off, the outside planking from the waterway seam to the light water mark scraped bright and treenails and bolts driven out for survey which proved good -
In consequence of worming - on port side, three fore hoods, six in midships and eight on buttock, on starboard side, three fore hoods, five planks in midships and six on buttock (all of wales) renewed with Pitch Pine and Baltic oak -
Recaulked from keel to seam inside waterway and resheathed with yellow metal on Felt - Windlass renewed with English Oak -
Lower deck beam ends wedged, Added to same six pairs of hanging knees and two pairs of riders -
The frame of this vessel was exposed nearly fore and aft in way of the wales removed, and proved in excellent condition

Present Condition of the

Decks	} good	Treenails	} good	Windlass and Capstan	good
Waterways		Breasthooks and Stemson		Pumps	} sufficient
Comings		Transoms, Pointers, and Crutches		Boats	
Upper Deck Beams & Fastenings	} good	Timbers of the Frame	} where seen	Masts, Yards, &c.	}
Lower Deck Beams & Fastenings		Keelsons		Sails	
Planksheers	} where seen	Clamps and Shelves	do	Anchors	No. of 3 x 1 x 2
Sheerstrakes		Ceiling	do	Cables	240 fms 1 1/2
Topsides	do	Rudder	do	Hawsers and Warps	} sufficient
Wales	do	Copper PLATE	When put on now	Standing & Running Rigging	
Plank (Bottom) and Counter	do				

General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways. *Good where tested*

This vessel has now been specially surveyed in strict conformity with the Rules. She is now in a good and efficient state of repair and is eligible in our opinion to be continued

3 A 1

The Amount of Fee.....£ 5: - : - is received by me,

Special..... 5: 5: -

Certificate (if required) : 5: -

Committee's Minute *7th January* 18 *62*.

Character assigned *Cont for 3 Years from 1861*

Thos. W. Wain
W. S. Munford