

Damage, Change of Owners &c 24550

REPORT of SURVEY for REPAIRS.

No. 157 Survey held at London Date Jan to March 8th 1862
 on the Barque Geo Washington Master William Dempster
 Tonnage 414 Built at Aberdeen When built 1837
 By whom built _____ Owners Messrs Escombe, Bro's
 Port belonging to London Destined Voyage Algoa Bay
 If Surveyed Afloat or in Dry Dock Lawender Dry Dock

Last Survey, No. 23458 Port London Classed 7th 1st

REPAIRS for damage &c - For particulars see Special Report -
 Now done, the keel hung in shores, and Caulked from
 the keel to the Gunwale, the waterways and a portion of
 the upper deck; a three inch false keel added after the
 lower side of the main keel had been trimmed over - the
 Windlass renewed with English Oak, a few trunnels
 driven out for examination and found satisfactory -
 her bottom resheathed with Yellow Metal on Fell -

The following not consequent upon damage -
 the lower part of the Rudder reduced, and the upper
 part made broader, the iron bolts at and under the
 metal line renewed with iron in sizes $\frac{7}{8}$ - 1 & 1 $\frac{1}{2}$.

Present Condition of the

Decks <u>Part Caulked</u>	Treenails <u>good when seen</u>	Windlass and Capstan
Waterways <u>Caulked</u>	Breasthooks and Stemson	Pumps <u>Good and</u>
Comings <u>good</u>	Transoms, Pointers, and Crutches	Boats <u>suff.</u>
Upper Deck Beams & Fastenings	Timbers of the Frame	Masts, Yards, &c. <u>new fore Mast</u>
Lower Deck Beams & Fastenings <u>firm</u>	Keelsons <u>Good when</u>	Sails
Planksheers	Clamps and Shelves <u>seen</u>	Anchors No. of <u>Good and</u>
Sheerstrakes <u>Caulked</u>	Ceiling	Cables <u>suff.</u>
Topsides	Rudder <u>Yellow Metal</u>	Hawsers and Warps
Wales	Copper <u>on Fell</u> When put on <u>now</u>	Standing & Running Rigging
Plank (Bottom) and Counter <u>Caulked</u>		

General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways.

Good when tested -
 She is now in good and efficient Condition, fit in
 my opinion to be retained as classed 7th 1st.

W. V. M. M. M.

The Amount of Fee.....£ 1 : - : is received by me,

Special..... 3 : - :

Certificate (if required) : - :

Committee's Minute 31st March 1862

Character assigned 7th 1st = record repair

Special damage fee £ 3. 3. 0
 extra attendance £ 3. 0. 0



© 2019

Lloyd's Register
 Foundation

LON645-0276