

24573

# REPORT of SURVEY for REPAIRS.

No. 211 Survey held at London Date 28<sup>th</sup> March 18 62  
on the H<sup>ts</sup> "Crystal Palace" Master John Marley  
Tonnage 480 Built at Seigamouth When built 1852  
By whom built \_\_\_\_\_ Owners J. Lidgett  
Port belonging to London Destined Voyage Cape Town  
If Surveyed Afloat or in Dry Dock Union dry dock & London Dock

Last Survey, No. 23841 Port London Classed 11 A 1

## REPAIRS

Now done; the ceiling from the fifth strake under the hold beams down to the lower part of bilges between the fore and mizen masts dubbed bright, three planks on starboard side renewed with Teak, three on port side and one forward with English Oak and Teak  
After the vessel was removed into the London Dock the owner had the upper deck waterways and strake next the same removed and renewed with Pitch Pine (10 ins) and the after shifts of main deck in way of the cant of raised quarter deck with the same, also the ship recaulked from metal line up -

### Present Condition of the

Decks <u>fit crew</u>	Treenails	Windlass and Capstan
Waterways <u>new</u>	Breasthooks and Stemson	Pumps
Comings	Transoms, Pointers, and Crutches	Boats
Upper Deck Beams & Fastenings	Timbers of the Frame <u>Good</u>	Masts, Yards, &c. <u>In good order</u>
Lower Deck Beams & Fastenings <u>Good</u>	Keelsons	Sails <u>and</u>
Planksheers <u>where seen</u>	Clamps and Shelves <u>where seen</u>	Anchors No. of <u>sufficient</u>
Sheerstrakes	Ceiling	Cables
Topsides	Rudder	Hawsers and Warps
Wales	Copper <u>YM</u> When put on <u>1860</u>	Standing & Running Rigging
Plank (Bottom) and Counter		

### General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways. good where tested

This vessel is now in good condition and is eligible in our opinion to remain classed A 1 the question with reference to use of lower classed material we beg respectfully to leave for the consideration of the committee

The Amount of Fee.....£..... is received by me,

Special.....2 : 2 : -

Certificate (if required).....

Committee's Minute 4<sup>th</sup> April 18 62

Character assigned

11 A 1 - record repair part 10 years  
x Memo. See Report Lon: 23861

Thos. W. Wain  
Lloyd's Register  
Foundation