

24686

REPORT of SURVEY for REPAIRS.

No. ~~135~~ 135 Survey held at London Date Apr 27th 1862
on the Ship "Hastings" Master M. Queen
Tonnage 535 Built at Sunderland When built 1855
By whom built _____ Owners Oliver & Co. No change
Port belonging to London Destined Voyage Montreal
If Surveyed Afloat or in Dry Dock Brodie's Dry Dock and London Dock

Last Survey, No. 23467 Port London Classed G A 1

REPAIRS of Damage now done, yellow-metal stripped, hung
in shores and caulked from keel to waterway seams
3 pairs of iron hanging knees fitted in hold where the
beam-ends had worked, strake of deck next the waterways
on each side taken up and a thick strake let down
over the beams and metal bolted through side of vessel,
yellow-metal renewed on felt. Counter ends re fastened.
Additional work, - vessel retreenailed from gunwale
to the upper part of the stow at floor beams.

Present Condition of the

Decks <u>good</u>	Treenails <u>partly renewed</u>	Windlass and Capstan <u>good</u>
Waterways <u>"</u>	Breasthooks and Stenson <u>"</u>	Pumps <u>"</u>
Comings <u>"</u>	Transoms, Pointers, and Crutches <u>"</u>	Boats <u>good and sufficient</u>
Upper Deck Beams & Fastenings <u>good</u>	Timbers of the Frame <u>good</u>	Masts, Yards, &c. <u>"</u>
Lower Deck Beams & Fastenings <u>where seen</u>	Keelsons <u>where seen</u>	Sails <u>"</u>
Planksheers <u>"</u>	Clamps and Shelves <u>"</u>	Anchors No. of <u>"</u>
Sheerstrakes <u>caulked</u>	Ceiling <u>"</u>	Cables <u>"</u>
Topsides <u>"</u>	Rudder <u>"</u>	Hawsers and Warps <u>"</u>
Wales <u>"</u>	Copper <u>7 in. When put on new done</u>	Standing & Running Rigging <u>"</u>
Plank (Bottom) and Counter <u>"</u>		

General Observations and Opinion, Caulking of Bottom, Deck, & Waterways. good where tested.
This vessel is now in good condition and in my
opinion eligible to remain as Classed G A 1.

The Amount of Fee.....£..... is received by me,
Special..... 3 3
Certificate (if required) 2 2
Committee's Minute 27th May 1862.
Character assigned Good - record repair
Damage put 3 3
Sp. Att. and Amce 2 2
J. F. Light
Lloyd's Register Foundation
LON645-0402