

24688

Change of Owners

REPORT of SURVEY for REPAIRS.

No. 143 Survey held at London Date Nov^r to Feb 4th 1862

on the Barge "The Bride" Master G. F. Warkmeister

Tonnage 546 Built at Sunderland When built 1836

By whom built _____ Owners Thos^r Wilson

Port belonging to London Destined Voyage Swan River

If Surveyed Afloat or in Dry Dock King & Queen Dry Dock & London Dock

Last Survey, No. 23756 Port London Classed 10A.1.
60

REPAIRS Now done, nine fore hoods of Ceiling on the Starboard bow, one timber, six chocks and five fillings new of English Oak & Teak - Two Iron Breasthooks taken down refitted and bolted - the yellow metal stripped off abreast of the new work, the trenails renewed thro' it, bottom where exposed caulked and the metal sheathing made good - The fore and main masts renewed, the pumps and windlass overhauled and made good - Her chain cables changed, examined and found good - 75 Tathoms added -

Present Condition of the

| | | |
|---|----------------------------------|-------------------------------------|
| Decks | Trenails | Windlass and Capstan |
| Waterways } <u>Good</u> | Breasthooks and Stenson | Pumps |
| Comings } | Transoms, Pointers, and Crutches | Boats |
| Upper Deck Beams & Fastenings | Timbers of the Frame | Masts, Yards, &c. } <u>Good and</u> |
| Lower Deck Beams & Fastenings } <u>Firm</u> | Keelsons | Sails } <u>ufft</u> |
| Planksheers | Clamps and Shelves | Anchors No. of |
| Sheerstrakes } <u>Good</u> | Ceiling | Cables |
| Topsides } | Rudder | Hawsers and Warps |
| Wales } | Copper } <u>Good</u> | Standing & Running Rigging |
| Plank (Bottom) and Counter | When put on <u>1860</u> | |

General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways: Good

She is now in good and efficient condition, fit in my opinion to remain classed 10A.1.
P. W. Waymouth

The Amount of Fee.....£ 2 : : is received by me,

Special.....£ 2 : 2 : 26/5/62

Certificate (if required) _____

Committee's Minute 27th May 18 62

Character assigned 10A.1
record repair



© 2019

Lloyd's Register Foundation

LONG45-0404