

* 24761

REPORT of SURVEY for REPAIRS.

Rec 6/6/62

No. 903 on the Ship "Mirage" Survey held at London Date 13th May to 3rd June 1862
Tonnage 256 Built at Hartlepool Master Roberts
By whom built Owners Ewing & Co
Port belonging to Liverpool Destined Voyage China
If Surveyed Afloat or in Dry Dock Ratcliff Croft dry dock

Last Survey, No. 23795 Port London. Classed 10 A1
3-61

Sow introduced to give increased strength

Two inner waterways of Pitch Pine one 14 in broad and 12 in deep, the other 12 in broad and 10 in deep hollowed out to form water course, rabbetted together and scored 1/4 in over the Beam ends fastened with Galvanized Iron Bolts through the three waterways and timber only, the yellow Metal fastenings of the original waterway remaining undisturbed, the up and down bolts are of Galvanized Iron driven well down and plugged; retreenailed from the under

Present Condition of the		P & S Over			
Keels	In good condition	Treenails	As New In good condition	Windlass and Capstan	As Good & Suff
Waterways	"	Breasthooks and Stemson	"	Pumps	2
Fastenings	"	Transoms, Pointers, and Crutches	"	Boats	4
Upper Deck Beams & Fastenings	"	Timbers of the Frame	where seen	Masts, Yards, &c.	"
Lower Deck Beams & Fastenings	"	Keelsons	"	Sails	D S
Planksheers	where seen	Clamps and Shelves	"	Anchors	No. of 3 B. 15. 1 K
Overstrakes	"	Ceiling	"	Cables	"
Upsides	"	Rudder	"	Hawsers and Warps	"
Staves	"	When put on	now done	Standing & Running Rigging	"
Plank (Bottom) and Counter	"				

General Observations and Opinion, Caulking of Bottom, Deck, & Waterways. good where tested

This vessel is in good and efficient condition eligible in my opinion to remain as Classed A1

The Amount of Fee.....£..... is received by me,

Special..... 3 : 3 : 0

Edwin R. Courchman

Certificate (if required).....

Committee's Minute..... 18.....

Character assigned.....



24761. Jan.

Side of Sheerstrakes to the Light Water line with Locust Treennails
& additional Iron Riders to Hold Beams, baulked from
Keel over all Deck included and resheathed with Galv.
Metal on felt

Edwin R. Blanchard



© 2019

Lloyd's Register
Foundation