

24787 Damage REPORT of SURVEY for REPAIRS.

No. 205 Survey held at London Date June 16th 1862
on the Barge "Reward" Master Newley
Tonnage 325 Built at Peterhead When built 1820
By whom built _____ Owners Sup^r J. Adams &
Port belonging to London Destined Voyage Montreal
If Surveyed Afloat or in Dry Dock Bridge Dry Dock & W. J. Dock

Last Survey, No. 24022 Port London Classified * F. 1 - S.S. 1834

REPAIRS

Now done. She has been hung in shores and Caulked from the keel to the bilges and to the shore heads forward and aft - and the yellow metal sheathing renewed from the keel to the bilges - the knee of head and fittings partly renewed, the Hawse pipes refitted, the bulwarks partly renewed, the deck house renewed and she has been Caulked from the metal line to the Centre of the upper deck.

Present Condition of the

Decks	<u>Caulked</u>	Treenails		Windlass and Capstan	
Waterways	<u>Caulked</u>	Breasthooks and Stemson		Pumps	<u>Good & Suff^r</u>
Comings	<u>Good</u>	Transoms, Pointers, and Crutches		Boats	
Upper Deck Beams & Fastenings	<u>firm</u>	Timbers of the Frame	<u>Good where seen</u>	Masts, Yards, &c.	<u>overhauled and made good</u>
Lower Deck Beams & Fastenings		Keelsons		Sails	
Planksheers		Clamps and Shelves		Anchors No. of	<u>Good and Suff^r</u>
Sheerstrakes	<u>Caulked</u>	Ceiling		Cables	
Topsides		Rudder		Hawsers and Warps	<u>one & two new</u>
Wales		Yellow metal		Standing & Running Rigging	<u>good</u>
Plank (Bottom) and Counter	<u>Part Caulked</u>	Copper <u>on felt</u>	When put on <u>last year</u>		

General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways. Good where tested
She is now in good Condition fit in my opinion for the safe conveyance of dry and perishable cargoes to and from all parts of the world and to remain as classed * F. 1 until the end of the Year if the Committee see no objection - P. W. Vaymouth

The Amount of Fee.....£ 1 : - : is received by me,

Special..... : - :

Certificate (if required) : 5 : -

Committee's Minute 22nd July 1862.

Character assigned F. 1 - omitting asterisk

Damage fee £ 2-2-0

© 2019

Lloyd's Register
Foundation

LON645-0500

April 1862

24th Aug 1862

Dr. 1 asterisk

until return from present voyage

and not beyond the end of the

year 1862

[Signature]



© 2019

Lloyd's Register
Foundation