

REPORT of SURVEY for REPAIRS.

+ Continuation

No. 187 on the 4th "Aeneas" Survey held at London Date 17th Dec^r 18 62
 Tonnage 339 Built at Bristol When built 1842
 By whom built _____ Owners Thomson & Co
 Port belonging to London Destined Voyage West Indies
 If Surveyed Afloat or in Dry Dock Nelson Patent Slip

Ref 232/12/63

Last Survey, No. 23027 Port London Classed 12 A 1
 Post 54 — 8 1.40

REPAIRS

at present under Special Survey Rule Sec 54, "the outside planking scraped bright from waterway seam to light water mark and trenails and bolts driven off for survey"
 Upper piece of stem renewed with Teak and one hold beam with English Oak - The lower blackstrakes fore and aft and garboard strakes also counter rails worked with thick stuff to House doubling (the frame exposed by same Rule 69 found good) the bottom caulked and made good Felted and doubled diagonally with 2¹/₂ in American Elm fastened with yellow metal - Rudder braces renewed, Recaulked, over - all and resheathed with yellow metal - Windlass stripped & examined - Bowsprit lifted, Foremast tongued and main mast renewed -

Present Condition of the

Decks	Good	Treenails		stripped & exp ^d	
Waterways	do	Breasthooks and Stenson	Good	Windlass and Capstan	
Comings	do	Transoms, Pointers, and Crutches	where	Pumps	
Upper Deck Beams & Fastenings		Timbers of the Frame	seen	Boats	
Lower Deck Beams & Fastenings		Keelsons	do	Masts, Yards, &c.	In good order
Planksheers	Good	Clamps and Shelves	do	Sails	and
Sheerstrakes	where	Ceiling	do	Anchors No. of	
Topsides	seen	Rudder	do	Cables	sufficient
Wales		Copper <u>SM on P</u> When put on <u>now</u>		Hawsers and Warps	
Plank (Bottom) and Counter				Standing & Running Rigging	

General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways. good where tested

This vessel is now in good condition and is eligible in our opinion to remain classed A 1 and be continued

3 A 1 from 1862

The Amount of Fee.....£ 4 : : is received by me,

Special..... 4 : 4 : c

Certificate (if required) : : c

Committee's Minute 26th December 1862

Character assigned

Cont A 1 for 3 years
record doubled



© 2019

Lloyd's Register
 Foundation

LON 646-0281