

REPORT of SURVEY for REPAIRS.

continuation

No. 880 on the

Survey held at

London

Date

Decr 24th 1862

on the

Yacht "County of Seafield"

Master

Pounder

Tonnage

492

Built at

Stockton

When built

1852

By whom built

Owners

Trail

Port belonging to

London

Destined Voyage

If Surveyed Afloat or in Dry Dock

Globe dry dock & St Katharines dock

Last Survey, No.

24009

Port

London

Classed

10 A 1

REPAIRS

Now under Special Survey Rule Sec 54 the outside plank - ing from the waterway seams to metal line scraped bright and tree - nails and bolts driven out for inspection (stripping to the light mark) - caused on owners application the caulking tested and found good - one plank of sheerstrake on each side in way of main chains renewed with Saw Bark, five top timbers, two rough trees and three filling timbers in wake of port fore chains renewed with English Oak one ceiling plank (two decks) new of Oak, the starboard quarter gallery and part rough tree rail renewed - Recaulked from metal line to waterway seams - Windlass stripped and found good -

Present Condition of the

Decks	} Good	Treenails	} Good	Windlass and Capstan	good
Waterways		Breasthooks and Stemson		Pumps	2
Comings	} Good	Transoms, Pointers, and Crutches	} where seen	Boats	2
Upper Deck Beams & Fastenings		Timbers of the Frame		Masts, Yards, &c.	sufficient
Lower Deck Beams & Fastenings	where seen	Keelsons	do	Sails	"
Planksheers	do	Clamps and Shelves	do	Anchors No. of	3 x 1 x 2
Sheerstrakes	do	Ceiling	do	Cables	sufficient
Topsides	do	Rudder	do	Hawsers and Warps	do
Wales	do	Copper	L & S M When put on 1861	Standing & Running Rigging	do
Plank (Bottom) and Counter	do				

General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways.

good where tested

This vessel has now been Specially Surveyed in strict conformity with the Rules Sec 54, she is now in a good and efficient state of repair and is eligible in our opinion to be continued

3 A 1 from 1862

The Amount of Fee.....£ 5 : - : - is received by me,

Special..... 3 : 3 : -

Certificate (if required) : 5 : -

Thos. W. Wain
John Maxwell

Committee's Minute 9th January 1863

Character assigned

Cont'd 1 for 3 years from 1862 record repairs

