

# REPORT of SURVEY for REPAIRS.

No. 586 Survey held at London Date Nov<sup>r</sup>. 22<sup>d</sup> 1862  
on the Barque Andromache Master H. Peirce  
Tonnage 468 Built at Scarboro' When built 1828.  
By whom built — Owners W. Vaughan & Co.  
Port belonging to London Destined Voyage Bermuda.  
If Surveyed Afloat or in Dry Dock Commercial Dry Dock.

*Seamans Report*  
Last Survey, No. 24,355 Port London. Classed A. 1.  
62

## REPAIRS

At this date from damage received by taking the ground near Cape Gracias on the 2<sup>d</sup> of May last in ballast.

Renew'd three lengths of main Keel, 14 x 14 R. Elm, three of Garboard Strakes, 3 1/2 in thick R. Elm. two strakes of doubling plank next the Garb'd. 2 1/2 in, and a hundred and fifty sheets of Linch on each side next the Keel. — put on two strakes of Linch higher up. Renew'd a short plank and Goe on the port Quarter, two gores in the starb'd buttock. — Caulk'd from Linch upwards, tested Caulking behind some sheets in the bottom it proves good. — Caulk'd the new work next the Keel, and gave her a good overhaul. —

## Present Condition of the

Decks	<u>in good order</u>	Treenails	<u>good</u>	Windlass and Capstan	<u>in good order</u>
Waterways	"	Breasthooks and Stemson	"	Pumps	"
Comings	"	Transoms, Pointers, and Crutches	"	Boats	"
Upper Deck Beams & Fastenings	"	Timbers of the Frame	"	Masts, Yards, &c.	"
Lower Deck Beams & Fastenings	"	Keelsons	"	Sails	"
Planksheers	"	Clamps and Shelves	"	Anchors No. of <u>2</u>	"
Sheerstrakes	"	Ceiling	"	Cables	"
Topsides	"	Rudder <u>efficient</u>	"	Hawsers and Warps	"
Wales	"	<u>and Sheathed</u>	"	Standing & Running Rigging	"
Plank (Bottom) and Counter	"	Copper <u>Linch</u> When put on <u>1862</u>			

## General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways. good.

Examined her outside and inside. Her sheer and appearance proving all good and efficient. I am of opinion she is fit to carry dry and perishable cargoes and eligible to remain as class'd A. 1.

The Amount of Fee.....£ 1 : — : — is received by me,

Special..... 2 : 2 : —

Certificate (if required) — : — : —

Committee's Minute 30<sup>th</sup> January 1863.

Character assigned A. 1

*Record damage repairs*



© 2019

Lloyd's Register Foundation

LON 646-0350