

25230

REPORT of SURVEY for REPAIRS.

S.S. for A.L. in Red first part

No. ³⁵ Survey held at London Date Nov 19th 1862
on the BK Yamar Master J. Ross

Tonnage 448 Built at Newport When built 1846

By whom built ✓ Owners J. Weller

Port belonging to London Destined Voyage Kurachee

If Surveyed Afloat or in Dry Dock in Bridge dock

On 10/12/62

Last Survey, No. 22985 Port London Classed 12 A1₆₀
Cont 58 4 yrs

REPAIRS

Stripped Yellow metal scraped and dubbed bright from light mark to Waterways inclusive and drove out bolts and treenails as per Rule Sec. 60

Renewed one length of Buttock plank on Port side and one length of forecastle drift of American Oak on Starboard bow; caulked from keel to gunwale and re-sheathed with Yellow metal over felt.

Windlass renewed and refitted with English Oak

Present Condition of the

Decks <u>Good</u>	Treenails <u>pt new</u> <u>Good</u>	Windlass and Capstan <u>Good</u>
Waterways <u>"</u>	Breasthooks and Stemson <u>"</u>	Pumps <u>"</u>
Comings <u>"</u>	Transoms, Pointers, and Crutches <u>"</u>	Boats <u>"</u>
Upper Deck Beams & Fastenings <u>"</u>	Timbers of the Frame <u>where seen</u> <u>"</u>	Masts, Yards, &c. <u>"</u>
Lower Deck Beams & Fastenings <u>"</u>	Keelsons <u>"</u>	Sails <u>"</u>
Planksheers <u>"</u>	Clamps and Shelves <u>"</u>	Anchors No. of <u>13, 15, 16</u> <u>"</u>
Sheerstrakes <u>"</u>	Ceiling <u>"</u>	Cables <u>"</u>
Topsides <u>"</u>	Rudder <u>"</u>	Hawsers and Warps <u>"</u>
Wales <u>"</u>	Copper <u>F & Y M</u> When put on <u>1862</u>	Standing & Running Rigging <u>"</u>
Plank (Bottom) and Counter <u>pt new</u>		

General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways. where tested Good

Is now in good and efficient condition fit for the safe conveyance of dry and perishable cargoes to and from all parts of the world, and having fully complied with the Rule Sec 60 (1st part) is in our opinion fit to be classed

A 1 in Red

The Amount of Fee.....£ 5 : : is received by me,

Special..... 3 : : 3 : -

Certificate (if required) : 5 : -

Committee's Minute 20th February 1863

Character assigned As in Red

accord repair



© 2019

Lloyd's Register Foundation

LON 646-0389

Taman



© 2019

Lloyd's Register
Foundation