

Continuation. REPORT of SURVEY for REPAIRS.

No. 467 Survey held at London Date Feb^y 23rd 1863
 on the Brig "Christiana Jarnell" Master Wm Rogers
 Tonnage 222 Built at Southampton When built 1850
 By whom built 193 Owners Brockenham
 Port belonging to Liverpool Destined Voyage West Indies
 If Surveyed Afloat or in Dry Dock in Ratcliff & St Katherine's Docks

Last Survey, No. 15895 Port Liverpool Classed 12 A1
59

REPAIRS

Yellow metal previously stripped; scraped bright from light mark upwards with part bottom and drove out bolts and treenails as per Rule Sec 54.

Renewed on Starbd side seventeen Top Timbers; two lengths of Sheerstrake; three of Topsides and one length of Wales of Teak and English Oak; two lengths of Planksheer and one Beam end of English Oak and one length of Flamp of Teak. On Port side two lengths of Sheerstrakes of Teak and one length of Wales of English Oak; caulked from Keel to Planksheer and resheathed with yellow metal over felt. Windlass stripped examined and found good.

Present Condition of the

Decks <u>Good</u>	Treenails <u>Good</u>	Windlass and Capstan <u>Good</u>
Waterways <u>"</u>	Breasthooks and Stemson <u>"</u>	Pumps <u>"</u>
Comings <u>"</u>	Transoms, Pointers, and Crutches <u>"</u>	Boats <u>"</u>
Upper Deck Beams & Fastenings <u>"</u>	Timbers of the Frame <u>Seen</u>	Masts, Yards, &c. <u>"</u>
Lower Deck Beams & Fastenings <u>"</u>	Keelsons <u>"</u>	Sails <u>"</u>
Planksheers <u>pt new</u>	Clamps and Shelves <u>"</u>	Anchors No. of <u>3 B, 1 S, 1 K</u>
Sheerstrakes <u>pt new</u>	Ceiling <u>"</u>	Cables <u>"</u>
Topsides <u>pt new</u>	Rudder <u>"</u>	Hawsers and Warps <u>"</u>
Wales <u>pt new</u>	Copper <u>FYM</u> When put on <u>1863</u>	Standing & Running Rigging <u>"</u>
Plank (Bottom) and Counter <u>"</u>		

General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways. when tested Good

Is now in good and efficient condition and having fully complied with the Rules Sec. 54 is in our opinion fit to be continued 4 A1

The Amount of Fee.....£ 2 : : is received by me, John Maxwell

Special..... 3 : 3 : 0 }

Certificate (if required) : 5 : - }

Thos. Wm. Hawn

Committee's Minute 9th March 1863

Character assigned Comp 12 for 14 years from 1862

© 2019

Lloyd's Register
Foundation

LON 646-0413