

25278

# REPORT of SURVEY for REPAIRS.

*Continuation*

No. 368 Survey held at London Date Feb. 10 to 14<sup>th</sup> 1863  
on the Shk "Trinidad" Master Wm Day

Tonnage 217 Built at Bristol When built 1834

By whom built \_\_\_\_\_ Owners Scrutton & Campbell

Port belonging to London Destined Voyage Martinique

If Surveyed Afloat or in Dry Dock Forms dry dock

Last Survey, No. 24410 Port London Classed 9 A1  
1-61

## REPAIRS

*Now done*

The yellow metal sheathing stripped off scraped or rubbed bright from the Light Water line over all Waterways included about 30 Greenails driven out for examination in the upper courses, scales, and topside. The limber boards and Air ports removed. The Windlap unhooked and the linings stripped off. An inner Waterway fitted of Greenheart 4 in thick and scored over the beams. Cables ranged. 18 fathoms new certificate produced.

The Decks, comings, beams, the frame Keelsons, Keel and Rudder, the planking inside and outside and all other parts where they could be seen, examined and found in good condition.

Present Condition of the

Decks	<u>good where seen</u>	Treenails	<u>good where seen</u>	Windlass and Capstan	<u>3 Over</u>
Waterways	"	Breasthooks and Stemson	"	Pumps	<u>2 Main &amp; 2 Bilge</u>
Comings	"	Transoms, Pointers, and Crutches	"	Boats	<u>3</u>
Upper Deck Beams & Fastenings	"	Timbers of the Frame	"	Masts, Yards, &c.	"
Lower Deck Beams & Fastenings	"	Keelsons	"	Sails	<u>20</u>
Planksheers	"	Clamps and Shelves	"	Anchors	No. of <u>3 B. 1 S. 2 K</u>
Sheerstrakes	"	Ceiling	"	Cables	"
Topsides	"	Rudder	"	Hawsers and Warps	"
Wales	"	<u>Copper on felt</u>	When put on <u>now done</u>	Standing & Running Rigging	"
Plank (Bottom) and Counter	"				

General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways. Good where tested

The Rules Section 34 have now been fully complied with. This vessel is in good and efficient condition eligible in our opinion to be continued on the A1 character.

The Amount of Fee.....£ 4 : - : is received by me, for three years


Special.....£ 4 : 4 : 0

Certificate (if required) \_\_\_\_\_

Committee's Minute 7th March 1863

Character assigned Cont'd 1 for 3 years  
no more repair

Edwint Couchman  
B. Raymouth



Lloyd's Register  
Foundation

LON 646-0430



25278. *Lon.*

*The sheer and general form of the ship is good*

*Caulked from keel to Metal line and  
resheathed with yellow Metal on felt*

*Edwin Bouchmann*



© 2019

Lloyd's Register  
Foundation