

# REPORT of SURVEY for REPAIRS.

No. 222 Survey held at London Date April 9th 1863  
 on the S. Murray Master John Roberts  
 Tonnage 718 Built at West Hartlepool When built 1855  
 By whom built Pile, Spence & Co Owners Living & Co.  
 Port belonging to Liverpool Destined Voyage China  
 If Surveyed Afloat or in Dry Dock in Ratcliffe Dock

Last Survey, No. \*24761 Port London Classed 10 A1  
3. 61

## REPAIRS

in consequence of damage see special report.

Stripped Yellow metal sheathing; hung in shores; renewed five lengths of plank in flat of bottom of American Rock Bln; thirty three of fore keel of English Bln; about sixty feet of false keel and two lengths of garboard strakes of American Bln; caulked from keel to Plankisheer and re-sheathed with yellow metal over felt.

Renewed windlass of Greenheart.

In consequence of decay, renewed one length of main keelson of Greenheart.

## Present Condition of the

Decks <u>Good</u>	Treenails <u>Good</u>	Windlass and Capstan <u>Good</u>
Waterways <u>"</u>	Breasthooks and Stemson <u>"</u>	Pumps <u>"</u>
Omings <u>"</u>	Transoms, Pointers, and Crutches <u>"</u>	Boats <u>"</u>
Upper Deck Beams & Fastenings <u>"</u>	Timbers of the Frame at the openings <u>"</u>	Masts, Yards, &c. <u>"</u>
Lower Deck Beams & Fastenings <u>"</u>	Ditto Ditto at other places <u>"</u>	Sails <u>"</u>
Plankisheers <u>"</u>	Keelsons <u>"</u>	Anchors No. of <u>3B, 1S, 1K</u> <u>"</u>
Garboard strakes <u>"</u>	Clamps and Shelves <u>"</u>	Cables <u>"</u>
Oppsides <u>"</u>	Ceiling <u>"</u>	Hawsers and Warps <u>"</u>
Rules <u>"</u>	Rudder <u>"</u>	Standing & Running Rigging <u>"</u>
Plank (Bottom) and Counter <u>pt new</u>	Copper <u>F &amp; Y M</u> When put on <u>1863</u>	
General Observations and Opinion,	Caulking of Bottom, Deck, & Waterways. <u>Good when tested</u>	

now in good and efficient condition and is in our opinion fit to remain as classed.

The Amount of Fee.....£ 2 : - : is received by me, John Maxwell  
 Special damage 4 : 4 : - Thos. H. Warton  
 Certificate (if required) : 5 : -

Committee's Minute 21st April 1863  
 Character assigned 10 A1

second damage report



© 2021

Lloyd's Register Foundation

LON 647-0071