

25485

REPORT of SURVEY for REPAIRS.

& Continuation

Recd June 63 18 63

No. 336 on the Bk "Sebastian" Survey held at London Date June 3rd 18 63 Master F. Little
Tonnage ~~426~~ 364 Built at Sunderland When built 1855
By whom built ~~W. J. Hall & Co.~~ Owners H. J. Hall & Co.
Port belonging to London Destined Voyage Natal
If Surveyed Afloat or in Dry Dock in Bridge & London docks

Last Survey, No. 24410 Port London Classed 7 A1 1. 62

REPAIRS

Stripped Yellow metal sheathing; scraped bright from light mark to waterways inclusive and drove out bolts and treenails as per Rule Sec 54

Renewed two lengths of main Keelson of Pitch Pine; nine lengths of ceiling on Starboard and five on Port side abaft; four lengths of ceiling on Starboard and three on Port side forward all of Red Pine and a deadwood knee of English Oak; re-fitted and bolted a crutch and added one of Iron; hung in shores; re-caulked from keel to waterways & re-sheathed with Yellow metal over felt; renewed many lower deck fastenings with Iron

The timbers where exposed by removal of ceiling were in good condition

Windlafs renewed with English Oak

Present Condition of the

Decks	Good	Treenails	pt new Good	Windlass and Capstan	new Good
Waterways	"	Breasthooks and Stemson	"	Pumps	"
Comings	"	Transoms, Pointers, and Crutches	pt new	Boats	"
Upper Deck Beams & Fastenings	"	Timbers of the Frame	at the Opening " here seen at other places	Masts, Yards, &c.	"
Lower Deck Beams & Fastenings	pt new	Do Do	pt new	Sails	"
Planksheers	"	Keelsons	"	Anchors	No. of 3 B, 1 S, 1 K.
Sheerstrakes	"	Clamps and Shelves	"	Cables	"
Topsides	"	Ceiling	pt new	Hawsers and Warps	"
Wales	"	Rudder	"	Standing & Running Rigging	"
Plank (Bottom) and Counter	"	Copper	F & Y M When put on 1863		

General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways. where tested Good

Is now in good and efficient condition and having fully complied with the Rules Sec. 54 is in our opinion fit to be continued 2 A1 from 1862.

The Amount of Fee.....£ 4 : - : - is received by me,

Special..... 4 : 4 : -

Certificate (if required) : 5 : -

Committee's Minute 9 June 1863

Character assigned Cont^d 1 yr 2 Years from 1862

H. J. Hall 148 Leadenhall St

Thos. M. Brown

© 2021

Lloyd's Register Foundation
LON647-0176