

25486

REPORT of SURVEY for REPAIRS.

Re 8/6/63
 No. 60 on the "Alexander" Brig Master H. Craig
 Survey held at London Date April to May 1st 1863
 Tonnage 206²¹/₁₀₀ Built at Prince Edwards Island When built 1862
 By whom built _____ Owners Burnley, James & Co.
 Port belonging to London Destined Voyage Trickarie
 If Surveyed Afloat or in Dry Dock Shooks Dry Dock and W. J. Docks.

Last Survey, No. 296 Port P.E. Isl. Classed 7. A.
62

REPAIRS now done.

Ship hung in shores and caulked from the keel to the copper line. Two pairs of iron pintles and braces taken off and new metal ones put on. Several iron bolts driven out of the bottom and renewed with copper. Sheathed with yellow metal on paper. The chain cables consist of 119 fathoms of 1¹/₆" tested to the required strain and 61 fathoms of 1" tested to 5 per cent over the strain. The testing certificates have been produced and found correct.

Present Condition of the

Decks	<u>Good</u>	Treenails	<u>Good</u>	Windlass and Capstan	<u>Trinch good</u>
Waterways		Breasthooks and Stemson		Pumps	<u>2 Bilge 3¹/₂ Lead</u>
Comings	<u>caulked</u>	Transoms, Pointers, and Crutches	<u>where</u>	Boats	<u>3 main 5¹/₂ Wood</u>
Upper Deck Beams & Fastenings	<u>where</u>	Timbers of the Frame at the openings		Masts, Yards, &c.	<u>good and sufficient</u>
Lower Deck Beams & Fastenings		Ditto Ditto at other places	<u>seen</u>	Sails	
Planksheers	<u>seen</u>	Keelsons		Anchors	No. of <u>5. 13¹/₂ 1. 14 1. 3. 1. 11</u>
Sheerstrakes		Clamps and Shelves		Cables	<u>180 fathoms 1¹/₆" 119 fathoms 1"</u>
Topsides		Ceiling		Hawsers and Warps	<u>good 100 fathoms 4¹/₂"</u>
Wales		Rudder	<u>in on</u>	Standing & Running Rigging	<u>sufficient</u>
Plank (Bottom) and Counter	<u>caulked</u>	Copper	<u>paper</u>		
General Observations and Opinion,		When put on	<u>now</u>		
		Caulking of Bottom, Deck, & Waterways.	<u>good where tested</u>		

She is in a good and efficient condition eligible in our opinion to be classed 7. A. 1

The Amount of Fee.....£ : : is received by me,

Special.....2:2:0

Certificate (if required) : 5: -

Committee's Minute 12th June 1863

Character assigned 7 A 1 record YM



© 2021

Lloyd's Register
Foundation

LON647-0178