

25806

# REPORT of SURVEY for REPAIRS.

Continuation 1<sup>st</sup> Survey

No. 70 Survey held at London Date Nov<sup>r</sup> 5<sup>th</sup> 1863  
on the S. "Parisian" Master Mourilyan  
Tonnage 749 Built at Kincardine When built 1854  
By whom built \_\_\_\_\_ Owners D' Oyley  
Port belonging to London Destined Voyage New Zealand  
If Surveyed Afloat or in Dry Dock Butannia Dock & E. Dock

Last Survey, No. 24683 Port London Classed S A 1 lapses 62

## REPAIRS

Now done; scraped bright from the third seam under the metal line to water way seam and treenails and bolts driven out for survey and found good. The caulking under the metal tested at various parts and found good and the remainder of the stripping to light mark dispensed with. See owners letter to the Committee.

Two beam arms to upper and one to lower deck renewed with Baltic Oak, lower deck clamp bolts and part lower deck waterway bolts renewed with Iron. Two planks in upper deck renewed and the main hatch enlarged. Recaulked from the third seam under the metal line over all and the two upper strakes of metal renewed on Felt. Windlass stripped & found good.

## Present Condition of the

Decks	Good	Treenails	Good where	Windlass and Capstan	good
Waterways	"	Breasthooks and Stenson	seen	Pumps	two of Iron
Comings	"	Transoms, Pointers, and Crutches	"	Boats	four good
Upper Deck Beams & Fastenings	"	Timbers of the Frame at the openings	"	Masts, Yards, &c.	"
Lower Deck Beams & Fastenings	"	Ditto Ditto at other places	"	Sails	sufficient
Planksheers	"	Keelsons	"	Anchors No. of	8 x 1 x 2
Sheerstrakes	"	Clamps and Shelves	"	Cables	30 fms
Topsides	"	Ceiling	"	Hawsers and Warps	sufficient
Wales	"	Rudder	"	Standing & Running Rigging	"
Plank (Bottom) and Counter	"	Copper <u>1 1/2 Y.M.</u> When put on <u>1862</u>			

## General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways. good where tested

This vessel has now been Specially Surveyed in strict accordance with the Rules Section 54. She is now in good and efficient condition and is eligible in our opinion to be continued S A 1 from 1862.

The Amount of Fee.....£ 5 : - : - is received by me,

Special..... 5 : 5 : -

Certificate (if required) : 5 : -

Committee's Minute 20<sup>th</sup> November 1863

Character assigned Cont A 1 for 3 Years from 1863



© 2021

Lloyd's Register  
Foundation

LONG 0464