

25813

REPORT of SURVEY for REPAIRS.

No. 650 on the S. "Colgrain" Survey held at London Date Nov^r 16th 1863
 Master Case
 Tonnage 623 Built at Cochin When built 1853
 By whom built _____ Owners Somes Bros.
 Port belonging to London Destined Voyage Algoa Bay & Calcutta
 If Surveyed Afloat or in Dry Dock Canal dock & W. S. Dock

Last Survey, No. 24868 Port London Classed 12 A 1
 8.62.

REPAIRS

Wood & metal sheathing stripped off; doubled with 2½ inch from wales to keel, the four upper strakes of Seat except after hoods of American Elm, and below ~~with~~ Wauzye Fir and American Elm: the whole of the doubling is on Felt and fastened with yellow metal butt bolts and treenails which are all through to lower part of bilge, the keelson bolts (where practicable have been driven out and the keelson ^{stem & stem post} refastened with yellow metal, the bilge keelsons have been additionally fastened with yellow metal every seven feet, also the throat and two bolts below of hanging knees and the Hook and crutch bolts renewed with yellow metal. Hung in shores recaulked from keel to metal line and resheathed with yellow metal on Felt. —
 Water resheathed three strakes (2ft 6in) with pine and American Elm on Felt.

Present Condition of the

Decks	<u>good</u>	Treenails	<u>good</u>	Windlass and Capstan	<u>good</u>
Waterways	"	Breasthooks and Stemson	"	Pumps	"
Comings	"	Transoms, Pointers, and Crutches	"	Boats	"
Upper Deck Beams & Fastenings	"	Timbers of the Frame	"	Masts, Yards, &c.	"
Lower Deck Beams & Fastenings	"	Keelsons	"	Sails	"
Planksheers	"	Clamps and Shelves	"	Anchors No. of	"
Sheerstrakes	"	Ceiling	"	Cables	"
Topsides	"	Rudder	"	Hawsers and Warps	"
Wales	"	Copper <u>12.5M</u> When put on <u>now</u>		Standing & Running Rigging	"
Plank (Bottom) and Counter	<u>doubled</u>				

General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways. good where tested

This vessel is now in good condition and is eligible in my opinion to remain classed

12 A 1

The Amount of Fee.....£ 2:—: is received by me,

Special..... 2: 2: —

Certificate (if required) : : —

Committee's Minute 24th November 1863

Character assigned 12 A 1

(A & C.P.) record repair



© 2021

Lloyd's Register Foundation

LON67-0471