

REPORT of SURVEY for REPAIRS.

Change of Owners.

No. 42 Survey held at London Date Oct. 30th Nov 21st 1863
 on the Barque Rangoon Master G. L. Pearnain
 Tonnage 384 Built at Sunderland When built 1853
 By whom built 113 Owners H. F. Taylor
 Port belonging to London Destined Voyage New Zealand

If Surveyed Afloat or in Dry Dock "Globe", low^r, dry dock.

Last Survey, No. 16793

Port Liverpool

Classed Cont^d 61 3 yrs. St. 1. 61

REPAIRS

as this date stripped off the yellow metal sheathing, drifted out some treenails on both sides from the bottom, bilges & and found them good, cut out a wormed part from the Post at the up^r end, and fitted a chock of English oak over it. - Condemned the Rudder, gave her a new main piece of Eng^h oak, and refitted it. Renewed four lengths of deck planks on the Starb^d, and three on the Port side in mid^ds. Fitted a temporary deck or platform on to the Hold Bms. Caulked the outside from Keel to wales, with deck and waterway seams and resheathed with yellow metal on felt. -

It appears that this vessel had some repairs last year on a Patent Slip at "Port Adelaide". - had twelve iron knees fitted to the Hold Beams, and was there stripped, resheathed and had sundry repairs as per bill at an expense of about £1200. -

Present Condition of the

Decks	in good order	Treenails	good	Windlass and Capstan	in good order
Waterways	"	Breasthooks and Stenson	"	Pumps	"
Comings	"	Transoms, Pointers, and Crutches	"	Boats	"
Upper Deck Beams & Fastenings	"	Timbers of the Frame at the openings	"	Masts, Yards, &c.	"
Lower Deck Beams & Fastenings	"	Ditto Ditto at other places	"	Sails	"
Planksheers	"	Keelsons	"	Anchors No. of 2	"
Sheerstrakes	"	Clamps and Shelves	"	Cables	Yanged on deck
Topsides	"	Ceiling	"	Hawsers and Warps	"
Wales	"	Rudder	New	Standing & Running Rigging	"
Plank (Bottom) and Counter	"	Wales felt & sheathed in 62.	1863.		
		Copper	on felt		
General Observations and Opinion,		Caulking of Bottom, Deck, & Waterways.	good where tested.		

This Vessel being now in good condition, I am of opinion

She is entitled to remain as Clasp'd Cont^d 3. A. 1.

Samuel Vernon.

The Amount of Fee.....£ 1 : - : - is received by me,

Special..... 2 : 2 : -

Certificate (if required) : 5 : -

Committee's Minute 1st December 1863

Character assigned Cont^d 3 A 1

Record repair



© 2021

Lloyd's Register Foundation

LON667-0487

Rangoon



© 2021

Lloyd's Register
Foundation.