

REPORT of SURVEY for REPAIRS.

Change of Owners.

No. 382
on the

Survey held at

London

Date

Nov. 27th (Dec. 1st) 1863

Ship *Severn*

Master

Craigie

Tonnage 475

Built at

Scarboro

When built

1847

By whom built

Owners

Addison & Co.

Port belonging to

London

Destined Voyage

New Zealand

If Surveyed Afloat or in Dry Dock

"Bull head" dry dock

Last Survey, No.

24208

Port

London

Classed

Cont^d 60. 4 A. 1. 13

REPAIRS

At this date stripped off the Yellow Metal Sheathing, brightened a good portion of the planks over down to light marks outside, inside in the fore peak also spotted them over bright. - drove out some few treenails for inspection (they proved good) Cut out a defective ceiling plank in the lower hold on the Starboard side, introduced one of English oak, also several gore pieces inside and outside. Hung her in shores, Caulked from keel to load line, also the deck and waterway seams and resheathed with Yellow Metal on felt up to 17 ft.

Present Condition of the

Decks	<i>in good order</i>	Treenails	<i>good</i>	Windlass and Capstan	<i>in good order</i>
Waterways	"	Breasthooks and Stenson	"	Pumps	"
Comings	"	Transoms, Pointers, and Crutches	"	Boats	"
Upper Deck Beams & Fastenings	<i>firm</i>	Timbers of the Frame at the openings	"	Masts, Yards, &c.	"
Lower Deck Beams & Fastenings	"	Ditto Ditto at other places	"	Sails	"
Planksheers	"	Keelsons	"	Anchors No. of 3	"
Sheerstrakes	"	Clamps and Shelves	"	Cables	"
Topsides	"	Ceiling	"	Hawsers and Warps	"
Wales	"	Rudder	<i>efficient</i>	Standing & Running Rigging	"
Plank (Bottom) and Counter	"	Copper Yell ^d Metal	<i>on felt</i>		

General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways. *good where tested*

This vessel being in good condition I am of opinion she is entitled to remain as classed Cont^d 4. A. 1. Samuel Pepin.

The Amount of Fee.....£ 1 : - : is received by me,

Special..... 1 : 1 : -

Certificate (if required) : 5 : -

Committee's Minute

15th December 1863

Character assigned

Cont^d 4 A. 1

record repairs

MA



© 2021

Lloyd's Register Foundation

LON647-0518