

# REPORT of SURVEY for REPAIRS.

No. in Reg. Book. **No.** 542 Survey held at London Date Jan 2<sup>nd</sup> 1864  
 on the Ship "Ellenborough" Master David Smith  
 Tonnage 926 Built at Newcastle When built 1842  
 By whom built \_\_\_\_\_ Owners G. Marshall  
 Port belonging to London Destined Voyage Calcutta  
 If Surveyed Afloat or in Dry Dock London Dock

Last Survey, No. 25878 Port London Classed Rest 61-8-1.

## REPAIRS

*Now done, her Chains and Anchors tested at the Society's works as follows.*

*Chains -*  
 152 Fathom of  $1\frac{1}{8}$  Tested to  $51\frac{3}{10}$  Tons  
 45 "  $1\frac{3}{8}$  " "  $47\frac{1}{2}$  "  
 90 "  $1\frac{3}{4}$  " "  $53\frac{1}{10}$  "  
 15 "  $1\frac{1}{2}$  " "  $40\frac{1}{2}$  "  
*Admiralty-Proof -*

*03 Fathoms -*

*Anchors - 22 Strick*  
 1st - 31" 0" 0" Tested to 29 Tons Regulation Proof 29" 7" 2" 0"  
 1st - 27" 3" 6" Tested to 27  $\frac{1}{16}$  " Regulation Proof 26" 19" 2" 21  
 1st - 25" 1" 0" " " 27  $\frac{1}{16}$  " " 24" 19" 1" 14

*The Two heaviest Anchors are Rogers' Make -*

*Part of the upper deck under the Fore castle has been renewed and Comings fitted round the Pall Butt -*

## Present Condition of the

Decks <u>Part Caulked</u>	Treenails	Windlass and Capstan
Waterways	Breasthooks and Stemson	Pumps
Comings <u>Good</u>	Transoms, Pointers, and Crutches	Boats
Upper Deck Beams & Fastenings	Timbers of the Frame at the openings	Masts, Yards, &c. <u>Good and</u>
Lower Deck Beams & Fastenings <u>Good</u>	Ditto Ditto at other places	Sails <u>Sufficient</u>
Planksheers	Keelsons <u>Good where</u>	Anchors No. of
Sheerstrakes <u>Good</u>	Clamps and Shelves <u>seen</u>	Cables
Oppsides	Ceiling	Hawsers and Warps
Vales	Rudder <u>Metal</u>	Standing & Running Rigging
Plank (Bottom) and Counter	Copper When put on <u>1862</u>	

## General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways. Good where seen

*It will be observed that Two of her Bower Anchors are rather lighter than prescribed by the Rules but have been tested beyond the Admiralty Proof - and a portion of her chains are smaller, but in my opinion she is found equal to her requirements, and therefore I recommend her to remain classed to 1. and the testing of the*

The Amount of Fee.....£..... is received by me,

Special..... : : :

Certificate (if required) : : :

Committee's Minute 15<sup>th</sup> January 1864

Character assigned Rest 8 B 1

*Anchors and Chains to be noted in the Registry Book.*

*B. Weymouth*



© 2019

Lloyd's Register Foundation

WON 648-0040