

REPORT of SURVEY for REPAIRS.

No. in Reg. Book. **No.** 250 Survey held at London Date Decr 15th 1863
 on the Barque Jannet. Master T. Thompson
 Tonnage 352 Built at Yarmouth When built 1834
 By whom built — Owners J. Robertson
 Port belonging to Shields Destined Voyage —
 If Surveyed Afloat or in Dry Dock "Bull head" dry dock.

Last Survey, No. 8737 Port Newcastle Classed 12 Δ Capred
Rest 57-8 hrs C 3 62

REPAIRS

At this date from damage &c. Stripped off the whole of the Yellow metal Sheathing. Scraped the outside planking bright down to light marks. Drove out some few treenails and bolts for inspection, they proved good, opened the air courses. Cut out listings inside. Lifted several decay'd ceiling planks. The timbers in various parts of the vessel (consecutively) proved unsound or defective. Hung her in shores. Caulked the outside, repaired the ceiling. Renew'd treenails and bolts both sides, but the Owner has declined renewing the Timbers pointed out, or going any further into the repairs.

Present Condition of the

Decks	Treenails	Windlass and Capstan
Waterways	Breasthooks and Stemson	Pumps
Comings	Transoms, Pointers, and Crutches	Boats
Upper Deck Beams & Fastenings	Timbers of the Frame at the openings	Masts, Yards, &c.
Lower Deck Beams & Fastenings	Ditto Ditto at other places	Sails
Planksheers	Keelsons	Anchors No. of
Sheerstrakes	Clamps and Shelves	Cables
Topsides	Ceiling	Hawsers and Warps
Wales	Rudder	Standing & Running Rigging
Plank (Bottom) and Counter	Copper When put on	

General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways.

We are of opinion that until this vessel is efficiently repaired, she is ineligible for the F. or any character.

The Amount of Fee.....£ : : is received by me,

Special..... 2 : 2 :

Certificate (if required) : :

Committee's Minute 19th January 1864

Character assigned

Record date of Survey

Samuel Vernon.

M. Wainwright



© 2019

Lloyd's Register
 LON GAP-0044

Jannet

REPORT OF THE LLOYD'S REGISTER FOUNDATION



© 2019

Lloyd's Register
Foundation