

Continuation 1st Rule 25939

REPORT of SURVEY for REPAIRS.

No. in Book. **No.** Survey held at London Date Jan 14th to 20th 1864
 on the Barge "Arca" Master W. Westcott
 Tonnage 350 Built at Waterford When built 1835
 By whom built 293 Owners Ships' Company &
 Port belonging to Dublin Destined Voyage Cape of Good Hope
 If Surveyed Afloat or in Dry Dock Mountain Dry Dock

Last Survey, No. 24867 Port London Classed SA 1. experienced

REPAIRS Now done A listing 4 wide cut out-pike ceiling on each side and at each end of her for a fifth of her length, all the timbers thus exposed, and those in the air courses, and where ever seen proved quite good; - bolts and treenails have been driven out as required from the yellow metal sheathing upwards. (Please see the Owners letter asking to be excused from stripping the yellow metal sheathing of her sides have been scraped bright from the metal sheathing to the waterway beam; the windlass stripped, examined, and found good; the chain cables ranged, examined and found good and sufficient. - Three ceiling planks each side in the run renewed with English Oak and a short piece of Hog Kelson forward renewed with Teak. - And she has been Caulked from the yellow metal to the gunwale.

P. S. O

Decks	Treenails	Windlass and Capstan
Waterways } <u>Good and</u>	Breasthooks and Stems	Pumps
Comings } <u>sufficient</u>	Transoms, Pointers, and Crutches	Boats
Upper Deck Beams & Fastenings	Timbers of the Frame at the openings	Masts, Yards, &c. } <u>Good and</u>
Lower Deck Beams & Fastenings } <u>Good</u>	Ditto Ditto at other places	Sails } <u>sufficient</u>
Planksheers	Keelsons	Anchors No. of
Sheerstrakes } <u>Scraped and</u>	Clamps and Shelves } <u>sufficient</u>	Cables
Topsides } <u>Caulked</u>	Ceiling } <u>where seen</u>	Hawsers and Warps
Wales	Rudder } <u>Good</u>	Standing & Running Rigging
Plank (Bottom) and Counter	Copper } <u>When put on 1862</u>	

General Observations and Opinion, Caulking of Bottom, Deck, & Waterways. Good where tested.
She is a good vessel fit in our opinion to be continued for 3 years A. 1. from 1863.


The Amount of Fee.....£ 3 : - - is received by me,

Special.....£ 4 : 4 :

Certificate (if required) : 5 : -

Committee's Minute 5th February 1864

Character assigned Good for 3 yrs from 1863



© 2019

Lloyd's Register Foundation

LCN 648 -00 65

25939 Lon

The upper deck and Comings, the upper and lower deck bolts, the blanking inside and outside, the timbers of the frame, stem, Apron, Knight heads, rowse timbers, Stern Post, Ladder, Windlass, beams, Keel and all other portions of her, where seen are in good Condition - Her Sheer and form are unaltered - N. Weymouth



© 2019

Lloyd's Register
Foundation