

# REPORT of SURVEY for REPAIRS.

No. in Reg. Book. **No.** 87 Survey held at London Date Dec<sup>r</sup> 29<sup>th</sup> 18 63  
 on the S. "Camperdown" Master J Cousins  
 Tonnage 993 Built at Sunderland When built 1847  
 By whom built \_\_\_\_\_ Owners Dunbar & Co Per Mess Jettatt  
 Port belonging to London Destined Voyage Calcutta  
 If Surveyed Afloat or in Dry Dock Canal dock

Last Survey, No. 24984 London Port Liverpool Classed 13 A 1  
 cont 60. - 4. 63

## REPAIRS In consequence of decay.

Nov<sup>r</sup> 16<sup>th</sup> Four after cant timbers on port side and ten after shifts of ceiling renewed with teak. Recaulked from keel to beam inside waterway and the yellow metal sheathing renewed on Felt, Bolsters and Hawse pipes taken out and refitted.

## Dec<sup>r</sup> 17<sup>th</sup> Damage

Yellow metal stripped, ship hung in stores, recaulked from keel to fourth beam on deck, two rough trees and the main channel on starboard side renewed, two lengths of Poop rail renewed and main bulwark repaired, Windlass untwung and spindle rewedged, resheathed with yellow metal on felt.

Added, four pairs of Iron riders forward, through bolted.

## Present Condition of the

Decks	Treenails	Windlass and Capstan
Waterways	Breasthooks and Stenson	Pumps
Comings	Transoms, Pointers, and Crutches	Boats
Upper Deck Beams & Fastenings	Timbers of the Frame at the openings	Masts, Yards, &c.
Lower Deck Beams & Fastenings	Ditto Ditto at other places <u>Good</u>	Sails
Planksheers	Keelsons	Anchors No. of <u>Good and sufficient</u>
Sheerstrakes	Clamps and Shelves	Cables
Topsides	Ceiling	Hawsers and Warps
Wales	Rudder	Standing & Running Rigging
Plank (Bottom) and Counter	Copper <u>L.F.Y.M.</u> When put on <u>now</u>	

General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways. good where tested

This vessel is eligible in our opinion to remain as classed A 1

The Amount of Fee.....£ 2 : - : - is received by me,

Special..... 2 : 2 : -

Certificate (if required) : : -

Committee's Minute 8<sup>th</sup> March 18 64

Character assigned Cont<sup>d</sup> 4 A 1

record repair

85

Thos W. Wain  
 John Maxwell



© 2019

Lloyd's Register Foundation

LONG 643 - 0129