

REPORT of SURVEY for REPAIRS.

No. in Reg. Book 856 No. 1 Survey held at London Date March 22^d April 2^d 1864.
 on the Schooner Susan Vittery Master Hendrick
 Tonnage 140 Built at Dartmouth When built 1859.
 By whom built Kelly Owners Vittery & Co.
 Port belonging to Brixham Destined Voyage Casting
 If Surveyed Afloat or in Dry Dock "Fountain" Dry Dock.

Last Survey, No. 1880 Port Dartmouth Classified 12. A. 1.
 61

REPAIRS

At this date from Collision. Renewed the upper Piece of Stem (English Oak). Refitted and rebuilt the Knee of the Head with Rails, lace piece, &c. &c. and all in connection. Gave her a New main Mast. refitted the Rigging. Stripped off the whole of the Yellow metal Sheathing. Cut out some Gore pieces in the bottom on the Starb^d side and removed defects. Caulked the outside from Keel to Gunwale. Tound the Stansions and Waterway Seams. Resheathed with Yellow metal on felt. and gave her a good overhaul inside and outside. -

Present Condition of the

Decks <u>in good order</u>	Treenails <u>good</u>	Windlass and Capstan <u>in good order</u>
Waterways <u>"</u>	Breasthooks and Stemson <u>"</u>	Pumps <u>"</u>
Comings <u>"</u>	Transoms, Pointers, and Crutches <u>"</u>	Boats <u>"</u>
Upper Deck Beams & Fastenings <u>"</u>	Timbers of the Frame at the openings <u>"</u>	Masts, Yards, &c. <u>"</u>
Lower Deck Beams & Fastenings <u>"</u>	Ditto Ditto at other places <u>"</u>	Sails <u>"</u>
Planksheers <u>"</u>	Keelsons <u>"</u>	Anchors No. of <u>3</u> <u>"</u>
Sheerstrakes <u>"</u>	Clamps and Shelves <u>"</u>	Cables <u>"</u>
Topsides <u>"</u>	Ceiling <u>"</u>	Hawsers and Warps <u>"</u>
Wales <u>"</u>	Rudder <u>efficient</u> <u>"</u>	Standing & Running Rigging <u>"</u>
Plank (Bottom) and Counter <u>"</u>	Gopper <u>Yell^d Metal</u> <u>on felt</u> <u>When put on</u> <u>now</u>	

General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways. Good

This Vessel having been efficiently repaired, and being now in good condition. I am of opinion She is entitled to remain as

Class'd 12. A. 1.

The Amount of Fee.....£ 10 : 10 : 0 is received by me,

Special..... 1 : 1 : 0

Certificate (if required) : :

Committee's Minute 12th April 18 64

Character assigned 12 A 1

record damage repair



© 2019

Lloyd's Register Foundation

LOV 648 - 0 189

Ref 4.4.66

Lillian V. H. H. H.



© 2019

Lloyd's Register
Foundation