

26149

REPORT of SURVEY for REPAIRS.

No. 723 Survey held at London Date Feb² to Mar 14th 1864
 on the Barque "Medina" Master John L. Bruen
 Tonnage 358 Built at Cowes When built 1837
 By whom built _____ Owners J. Shepherd
 Port belonging to London Destined Voyage Japan
 If Surveyed Afloat or in Dry Dock Union Dry Dock

Last Survey, No. 25943 Port London Classed 13A

REPAIRS

for damage &c - How done, the yellow metal sheathing renewed upon Sell - Six planks of bottom on the port side of bottom renewed with Rock Elm; the Iron Keel trimmed up and a ^{new} false keel added of English Elm fastened with 15 Yellow Metal $\frac{3}{4}$ inch dump bolts, and with such this bolts in way of the ship's keel scarp - also a ^{new} false keel added fastened to the ^{new} one with keel staples. The keel hung in shores and caulked with metal sheathing line - 30 fathoms of $1\frac{3}{8}$ inch Chain Cable tested to 34 tons and a Bower Anchor 16.1.12 tested to 17 $\frac{1}{2}$ tons and a Kedge Anchor have been supplied to her by Messrs Brown, Lennox & Co in lieu of the same amount lost - The above Anchor and Chain tested to Admiralty Proof -

Present Condition of the

Decks	Treenails	Windlass and Capstan
Waterways } <u>Good</u>	Breasthooks and Stemson	Pumps
Comings	Transoms, Pointers, and Crutches	Boats
Upper Deck Beams & Fastenings	Timbers of the Frame	Masts, Yards, &c. <u>Good and</u>
Lower Deck Beams & Fastenings } <u>Good</u>	Keelsons	Sails <u>Sufficient</u>
Planksheers	Clamps and Shelves	Anchors No. of
Sheerstrakes	Ceiling	Cables
Topsides } <u>Good</u>	Builder's Metal	Hawsers and Warps
Wales	Copper on Sell When put on <u>How</u>	Standing & Running Rigging
Plank (Bottom) and Counter <u>Caulked</u>		

General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways.

She is now in good and efficient Condition fit in my opinion to be retained as classed 13A.

B. W. W. W. W.

The Amount of Fee.....£ 1 : - : is received by me,

Special.....£ 2 : 2 : -

Certificate (if required) : : -

Committee's Minute 20th May 1864

Character assigned 13A

Damage fee £ 5. 5. 0



© 2019

Lloyd's Register Foundation

8720-87307