

25512

26159

REPORT of SURVEY for REPAIRS.

2nd Survey for A 1 in RedNo. in Reg. Book, No. 607 Survey held at London Date Sep 7th Oct 29/63 April 8th 1864on the B⁷ Spheroid Master

Tonnage 2574 Built at Bermuda When built 1826

By whom built Owners Scrutton & Sons

Port belonging to London Destined Voyage West Indies

If Surveyed Afloat or in Dry Dock Afloat West India & London Dock

Last Survey, No. 25512 Port London. Classed 9th Dec 1863 11 May 1863

REPAIRS

Scraped bright from metal line to waterway seam (the bottom under the metal having been passed see London Report 25512.) opened by the removal of the waterways from the raised quarter deck to the windlass and by a ceiling plank taken out from thence forward and aft. Cabins entirely removed and the transoms and beam ends bored a listing cut out all fore and aft at the floor heads, bolts of doubling driven out and found good, and the windlass stripped and examined.

The waterways removed renewed with Greenheart and two stakes of deck next the same new of Red pine, the main, main-topmast and topgallant masts renewed also the pumps Recaulked from metal over all.

Present Condition of the

Decks	good	Freenails Bolts	good	Windlass and Capstan	good
Waterways	pt new	Breasthooks and Stimson	"	Pumps	new
Comings	"	Transoms, Pointers, and Crutches	"	Boats	two
Upper Deck Beams & Fastenings	"	Timbers of the Frame at the openings	"	Masts, Yards, &c.	pt new
Lower Deck Beams & Fastenings	"	Ditto Ditto at other places	"	Sails	sufficient
Planksheers	"	Keelsons	"	Anchors	No. of 3 x 1 x 1
Sheerstrakes	"	Clamps and Shelves	"	Cables	210 fms
Topsides	"	Ceiling	"	Hawsers and Warps	sufficient
Wales	"	Rudder	"	Standing & Running Rigging	"
Plank (Bottom) and Counter	"	Copper	When put on 1863		

General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways. good

This vessel is now in a good and efficient state and fit for the conveyance of dry and perishable cargoes to and from all parts of the world; & having now complied with all the requirements of the Rules See 66, 2nd survey we respectfully recommend

The Amount of Fee.....£ 3 : - : is received by me, her to be classed

Special..... 4 : 4 : -

Certificate (if required) : : -

Committee's Minute 24th May 1864

Character assigned

A 1 in Red

S. S. 43 - 4 years record repair

and marked SS 67 6 yrs

2019
 The Register
 Foundation
 LON 648 - 0 259