

# 26359 ~~26255~~ REPORT of SURVEY for REPAIRS.

No. in Reg. Book. **No.** 296 Survey held at London Date June 8<sup>th</sup> 14<sup>th</sup> July 18<sup>th</sup> 64  
on the Ship Robert Morrison Master James McQueen Spinks  
Tonnage 555 610 Built at Sunderland. When built 1853.  
By whom built — Owners Wilson &  
Port belonging to London Destined Voyage Hobart Town.  
If Surveyed Afloat or in Dry Dock "Princes" dry dock.

Last Survey, No. 23021 Port London. Classed 13. A. 1.  
60

## REPAIRS

At this date stripped off the whole of the Yellow Metal Sheathing, drove out a few treenails on the Starb. side found bad at the points. also split out in midships below the Hold beams two defective lengths of "stringy bark" plankling. Lifted the Lumber boards opened the air courses. Examined Floors, Timbers, Keelson &c. and all proved sound where seen. Introduced two new lengths of Teak planks to the lower Hold Ceiling. Hung her in shores. Caulked the outside from Keel to Gunwale. And Resheathed with Yellow Metal on felt and gave her a good overhaul. —

## Present Condition of the

Decks <u>in good order</u>	Treenails <u>good</u>	Windlass and Capstan <u>in good order</u>
Waterways <u>"</u>	Breasthooks and Stemson <u>"</u>	Pumps <u>"</u>
Comings <u>"</u>	Transoms, Pointers, and Crutches <u>"</u>	Boats <u>"</u>
Upper Deck Beams & Fastenings <u>"</u>	Timbers of the Frame at the openings <u>"</u>	Masts, Yards, &c. <u>"</u>
Lower Deck Beams & Fastenings <u>"</u>	Ditto Ditto at other places <u>"</u>	Sails <u>"</u>
Planksheers <u>"</u>	Keelsons <u>"</u>	Anchors No. of <u>3</u> <u>"</u>
Sheerstrakes <u>"</u>	Clamps and Shelves <u>"</u>	Cables <u>"</u>
Topsides <u>"</u>	Ceiling <u>"</u>	Hawsers and Warps <u>"</u>
Wales <u>"</u>	Rudder <u>efficient</u> <u>"</u>	Standing & Running Rigging <u>"</u>
Plank (Bottom) and Counter <u>"</u>	Copper <u>Yellow Metal</u> When put on <u>now</u> .	

General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways. good

I am of opinion this Vessel is entitled to remain  
as Class'd 13. A. 1.

Samuel Vernon.

The Amount of Fee.....£ 2 is received by me,

Special..... 1 : 1 :

Certificate (if required) —

Committee's Minute 13<sup>th</sup> September 18 64.

Character assigned 13 A. 1

MM record repair



© 2019

Lloyd's Register  
Foundation

LOU 618 - 0 429